


[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1901, by Munn & Co.]

Vol. LXXXIV.—No. 26.  
ESTABLISHED 1845.

NEW YORK, JUNE 29, 1901.

[ \$3.00 A YEAR.  
8 CENTS A COPY.



# Scientific American.

ESTABLISHED 1845

MUNN &amp; CO., - - - EDITORS AND PROPRIETORS.

PUBLISHED WEEKLY AT

No. 361 BROADWAY, - - - NEW YORK.

## TERMS TO SUBSCRIBERS

One copy, one year, for the United States, Canada, or Mexico ..... \$3.00  
 One copy, one year, to any foreign country, postage prepaid, 80 cts. ad. 4.80

## THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (Established 1845) ..... \$3.00 a year  
 Scientific American Supplement (Established 1850) ..... 5.00 "  
 Scientific American Building Edition (Established 1893) ..... 2.50 "  
 Scientific American Export Edition (Established 1859) ..... 5.00 "

The combined subscription rates and rates to foreign countries will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.

MUNN & CO., 361 Broadway, corner Franklin Street, New York.

NEW YORK, SATURDAY, JUNE 29, 1901.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

## BIGGEST IN THE WORLD.

Is it because we never entirely lose some of the strong characteristics of childhood that, in describing an event or an object, we seem to consider that the last touch of dignity and importance has not been put upon it until it has been designated as the biggest or most superlative something or other of its kind in the world? It is really surprising how much heart-burning may be caused by a journalistic inadvertency, actual or supposed, in placing the coveted honor where it does not belong. A curious instance of an imagined injustice of this kind has lately reached the Editor's desk in the form of an editorial from our esteemed contemporary, The Daily Eagle of Poughkeepsie, N. Y., in which the writer takes us to task for having stated that the new double-track railway viaduct over the Des Moines River, Iowa, is in some respects the most notable railway viaduct in existence. This structure is 2,685 feet in length, and its rails are 185 feet above the water. The peace of mind of our Poughkeepsie contemporary has been rudely disturbed by our stating that this structure, "in point of the total weight of metal employed in its construction, is fully three times as heavy as the next largest bridge of the kind in the world." The statement is unpardonable in the eyes of our critic, who hastens to remind us that he lives beneath the shadow of a double-track railway bridge, which is 6,767 feet and some inches in length, and 212 feet above high tide, and contains a dead-weight of over 21,000 tons of steel as against the insignificant total of 5,680 tons that was built into the structure over the Des Moines River. The trouble with our contemporary is that he is comparing two horses of an entirely different color, namely, a viaduct and a cantilever, the Des Moines crossing being of the first and the Poughkeepsie crossing of the second type. In bridge engineering parlance it is customary to classify a bridge according to the predominant feature thereof. In the case of railway bridges, such as the Loa viaduct in Bolivia, and the Kinzua and Pecos viaducts in this country, where by far the greater part of the crossing is made up of short spans carried on steel bents or braced towers, with or without a truss span thrown across the main channel, or gorge, as the case may be, the structure takes its name from its predominant feature and is known as a viaduct, this term being generically applied to any tower-and-short-span structure of the kind described. On the other hand, a bridge of the character of the Forth cantilever structure in Scotland, or the Poughkeepsie crossing of the Hudson, in which the cantilevers form the predominant feature and the viaduct approach, great as it may be, is entirely subsidiary, the structure is generically known as a cantilever bridge. The same may be said of the new East River bridge, which, although it is approached by a viaduct several thousands of feet in length—of an aggregate length indeed much greater than that of the suspended structure—will nevertheless be known as a suspension bridge. For all its 4,000 and more feet of viaduct, the splendid structure at Poughkeepsie will ever be known as one of the great cantilever bridges of the world.

## EXTRAORDINARY SPEED IN THE PARIS-BORDEAUX AUTOMOBILE RACE.

From Paris to Bordeaux by road is a distance of 349 miles, and when the great chauffeur Charron covered this distance in the race of 1900 in 11 hours 4 minutes and 20 seconds, at an average speed of 31.4 miles per hour, it was justly considered to be a most remarkable performance. This year, however, has witnessed a feat which is not only the most sensational in the annals of automobilism, but one of the most remarkable speed performances of any kind whatever, whether by road, rail or sea; for the same dis-

tance was covered by the winner in 8 hours 44 minutes and 44 seconds, at an average speed of about 40 miles an hour. The significance of this performance is only understood when we bear in mind that the Paris-Bordeaux course involves a reduction of running speed to about 7½ miles an hour in passing through ten different towns and cities along the route. If the 18 miles on which there is a speed restriction be deducted, we find that Fournier covered 330 miles in 6 hours 11 minutes and 44 seconds, at an average speed of more than 53 miles an hour. Remembering that in climbing the hills and on certain parts of the road where curvature or other local conditions would necessitate it, the speed must have been brought down very much below this average, we can see that, on certain stretches, the automobile must have been running at a speed of from 70 to 75 miles an hour—and this, be it remembered, upon a country macadamized road and not upon a carefully aligned steel track, fenced in from all the risks and dangers of miscellaneous traffic. Interest in this performance centers both in the man and the machine. The latter was a Mors vehicle of 35-horse-power, and, unprecedented as was this capacity, it was excelled in some of the other machines that were present at the starting line, the English automobilist Edge, for instance, being on hand with a 70-horsepower machine, which was disqualified on the ground that the tires, which had been substituted on account of a puncture, at the last moment, were of French and not of English make. The machine thereby failed to meet the conditions of the race, which demanded that each machine should have an absolutely national character. Judged on purely technical and mechanical grounds there is, of course, no reason why an automobile provided with sufficient horsepower should not maintain such high speeds and even higher speeds for as great and greater distances; and we say this without wishing to detract from the great credit which is due to the builders of the leading vehicles, several of which made better time than that accomplished by the winner of last year's race.

The most remarkable feature of the whole performance is the nerve and skill possessed by the chauffeur Fournier, for at the terrific pace achieved, it is evident that the slightest error in judgment could easily have precipitated disaster. Full details of the race will be read with considerable interest, particularly as regards the special policing, which must surely have been carried out at crossroads and elsewhere to maintain some kind of a clear track ahead of machines that were sweeping along at speeds faster than those of the average express train. Fournier is well known in this country. Only a couple of years ago he was a conspicuous figure upon the bicycle track at Madison Square Garden, where he exhibited a motor-cycle and introduced motor-pacing to the American public.

It is noteworthy that the leading automobiles were all heavy vehicles of great power, the first five being in the class weighing over 1,430 pounds. The winning machine was, as we have said, a Mors, and the second, third, fourth and fifth were Panhard vehicles. The sixth and seventh contestants to finish were 8-horsepower De Dion motor-cycles, the first covering the distance in 8 hours 13½ minutes and the second in 8 hours 3 minutes. An average speed of over 40 miles an hour for 330 miles for a motor-bicycle is a scarcely less remarkable feat in its way than that of the winning machine.

## THE LESSON OF THE RECENT FERRYBOAT DISASTER.

It is to be feared that the relatively small loss of life in the recent ferryboat collision in New York Harbor, small, that is to say, compared with the loss which might easily have occurred, may result in our too readily forgetting the lesson which this accident teaches. Had the Staten Island ferryboat been rammed by the "Mauch Chunk" when she was far from her berth, instead of being fortunately within reach of shoal water, the list of fatalities would probably have run up into the hundreds.

It is not for us to enter into the question of culpability in this accident: that will be decided by the proper authorities and the blame, if there be any, will be placed where it rightly belongs. Moreover, when we bear in mind the enormous number of passengers carried every year by our ferryboats, the crowded state of the New York waterways, and the fact that the ferryboats make their trips directly across the line of travel of incoming and outgoing ships, we must admit that the freedom from accident is something truly phenomenal and reflects the highest credit upon the skill of our ferryboat pilots. Shipping men from all over the world have commented upon the extraordinary care required in the navigation of the stretch of water that embraces the southern end of Manhattan Island, and have spoken in the highest terms of the skill which is shown by the captains and pilots of our local craft. Having said this much, however, there is one lesson of the "Northfield" disaster upon which we would lay very special emphasis, and this is that in view of the ever present possibility of collision, all ferryboats at the port of New York should be built with a view to their pos-

sessing a wide margin of flotation, their hulls being so subdivided by bulkheads that they would be incapable of being quickly sunk, as was the "Northfield," by a single blow beneath the water line. The more modern ferryboats, of course, are constructed on this plan; but there are some of the older boats around New York, which, if they should be run down, would have great difficulty in reaching shoal water before they sank. We trust that one result of this disaster will be the enactment of even more stringent regulations as to the construction and subsequent inspection of all craft employed in the ferry service around this city.

## THE NEW CLYDE LINE STEAMSHIP "APACHE."

It is probably due to the great size and high speed of the transatlantic liners, and the interest of the American public in their performances, that we are in danger of forgetting that our American coastwise steamship companies are adding steadily to their fleets and putting some very serviceable and thoroughly up-to-date new boats upon the various routes. There sailed from this port last week the Cramp-built liner "Apache," the first of two sister ships which have been built by that company for the Clyde Line for service on the route between this port, Charleston, S. C., and Jacksonville, Fla. The "Apache," which is the seventeenth steamship of the company's fleet, is slightly larger than the "Comanche," "Algonquin" and "Iroquois," of the same service. She is 310 feet long, 46 feet beam and 31 feet deep. She is driven by triple-expansion engines with cylinders 25, 43 and 70 inches in diameter and 36 inches stroke, and is built to steam 15 knots when loaded to her full capacity of 3,000 tons of cargo. The staterooms are characteristically American, that is to say, they are spacious, well lighted and airy, and they are free from that too-profuse decoration with which modern passenger ships are apt to be overloaded. There is accommodation for 200 passengers, all of which is above the upper deck.

## RECONSTRUCTION OF GERMAN CRUISERS.

The German navy has recently undertaken an important piece of work, which consists in modifying a series of eight cruisers which form part of the fleet so as to increase their tonnage and bring the construction up to date. This is to be carried out in a somewhat novel fashion by lengthening the hull by some 25 feet, cutting it in the middle and adding a central portion. This has already been carried out with the first of the series, the "Hagen," and the results have proved so successful that there is little doubt that the remaining seven will be treated in the same manner. The series of cruisers includes the "Hagen," "Frithjof," "Beowulf," "Hildebrand," "Siegfried," "Heimdall," "Aegir" and "Odin." They are coast defense cruisers which were designed at a period when the German navy was mainly occupied with the defensive, and in consequence these boats, which were to navigate along the coast and keep within a short distance from supply points, carried only a small provision of coal, this being about 220 tons. Their displacement was reduced as much as possible, this being just sufficient to comply with the requirements of this class of boats. Six of these cruisers proved quite satisfactory in service, and gave proof of remarkable nautical qualities, and it was thereupon decided to increase the number from six to eight; the latter two had a displacement somewhat greater than the others, and the power and coal supply was thus increased. However, with the recent increase of the German navy and a new order of ideas, these boats were judged to be quite insufficient to figure in the present fleet. But if their radius of action was limited, their other qualities showed that they were fitted to perform the duties of first class cruisers, and it was accordingly decided to transform them by increasing their coal-capacity and thus add a series of boats to the fleet at a relatively small cost, and as the oldest of these dates only from 1889, they will be still quite modern. To increase the coal capacity, the displacement, and consequently the length of the boat, was to be increased. This operation, which is comparatively easy on an ordinary steamer, presents certain difficulties in the case of an armored vessel; in order to cut it in the middle and add the amount required for the increased displacement, it is necessary that as few of the parts as possible should be dismantled in the two halves, which should be left in their original condition, thus leaving in place the engines and boilers, etc. It was decided to commence the work with the "Hagen," and this was begun at the Kiel docks in September, 1899. The section was made in front of the engines, and the rear part was drawn back about 26 feet; the operation of moving the mass required less than an hour. The intermediate portion which was added represented a weight of 500 to 600 tons. In October, or about a year after the commencement of the work, the "Hagen" proceeded with its trials, with very satisfactory results; the engines and boilers acted well, and developed 5,280 horse power, the number of requ-



lutions being increased to 142 per minute. The coal supply, owing to the increased displacement, has been raised from 220 to 500 tons, and a number of minor changes have been made which give the boat an up to date appearance. The coasting cruisers, when thus transformed, will be able to take an active part with the remainder of the fleet, and there is no doubt that the whole series will be thus treated. To transform the eight vessels will cost about five millions, according to calculations, this representing the cost of a single modern battleship, and the advantage is at once apparent.

#### THE HEAVENS IN JULY.

BY HENRY MORRIS RUSSELL, Ph.D.

The brightest stars in the summer skies are the ruddy Arcturus and the bluish Vega. At 9 P. M. on July 15 the former is some distance west of the zenith, and the latter somewhat nearer on the east. Between them lie the constellations of Corona Borealis and Hercules, the first of which consists of a semi-circle of inconspicuous stars, and the second of a keystone-shaped group directly overhead, with outliers on both sides. South of these a large area is filled by the intermingled forms of Ophiuchus and Serpens, whose most characteristic configuration is a kite-shaped figure a little west of the meridian.

Close above the southern and southeastern horizon are Scorpio and Sagittarius. The bright red star Antares, and the long, curving line below it which forms the Scorpion's tail, cannot be mistaken; and Sagittarius, which is anyhow one of the more conspicuous zodiacal constellations, now includes within its borders both Jupiter and Saturn.

Aquila, marked by the brilliant Altair, with a fainter attendant on each side, is well up in the southeast. Below it is Capricornus, whose two brightest stars both show double in a field-glass. Cygnus is conspicuous in the Milky Way below Vega. Farther down on the right is the little group of Delphinus, often called "Job's Coffin." Pegasus and Andromeda are rising in the northeast. Of the circum-polar constellations, Cassiopeia is below and to the right of the pole, Cepheus higher up, Draco and Ursa Minor above the pole-star, and Ursa Major on the left. Leo, Virgo and Libra fill most of the western and southwestern sky.

The present is a good opportunity for the study of some interesting variable stars. First among these may be mentioned Beta Lyrae, which is the nearest to Vega of a pair of small stars which lie on the line joining it with Altair, about one-quarter as far as the latter. The changes of its brightness may be easily observed by comparing it with its neighbor, Gamma Lyrae. They are completed in 12 days 21½ hours, during which time there are two equal maxima of brightness, separated by two unequal minima. Beginning at the first maximum, its magnitude is 3.4, about equal to Gamma. Then it falls nearly to the fourth magnitude, rises again to its original brightness, and descends once more to the 4½ magnitude, returning finally at the end of the period to its initial condition. The star's spectrum also shows remarkable peculiarities, containing both dark and bright lines, which are periodically displaced with reference to one another in such a way as to show that they are produced by two different bodies revolving about one another in a period equal to that of the light-variation.

The following explanation of the star's variability, deduced from the above-mentioned facts, is taken from an article by Mr. Myers, published some time ago in the *Astrophysical Journal*. Beta Lyrae consists of two stars, one about three-quarters the diameter of the other, revolving about one another, in a circular orbit, so close together that they almost touch. The plane of this orbit is inclined very little to the line of sight, so that the stars alternately eclipse one another. The smaller star is nearly twice as bright as the larger one.

At the principal minimum, the small star is behind the larger one, and only the light of the latter reaches us. Three days later it is on one side, and the combined light of both stars produces a maximum. After about three days more the small star is in front of the large one, hiding most of it. All the light of the small star and part of that of the large one reaches us, so that, though the star does not appear to us as bright as at maximum, it is much brighter than at the principal minimum. When the small star has moved off on the other side we have a second maximum. The actual velocities of the stars in miles per second can be determined from the spectroscopic observations, and thus it is found that the centers of the two stars are about 30,000,000 miles apart. The larger star is over 30,000,000 miles in diameter, and is about 21 times as heavy as our sun. The diameter of the smaller one is about 23,000,000 miles, and its mass nearly 10 times that of the sun. Their bulk, in proportion to their mass, is enormous, so that they must be entirely gaseous and hardly denser than the earth's atmosphere at sea-level.

Two other short-period variables are now in good position for observation. On the upper edge of the Milky Way, about midway between Cygnus and Cassiopeia, is a triangle of small stars. The nearest one to Cassiopeia is Delta Cephei, which varies between the magnitudes 3.7 and 4.9 in 5 days, 8 hours and 48 minutes. The other two stars of the triangle are good "comparison stars."

To find the other variable, start with Altair. A line drawn from the small star above it through the fainter one below it, and continued as far again, bending sharply to the right, points out Eta Aquilae. The period of this star is 7 days, 4 hours and 14 minutes, its maximum magnitude is 3.5, and its minimum 4.7.

The variation of both these stars is of the same type. The brightness changes continuously, rising rapidly to the maximum, and falling off much more slowly toward the minimum. In the case of Eta Aquilae a slight rise to a secondary maximum interrupts the falling phase. Such variation evidently cannot be due to eclipses, as the times of fall and rise would in that case be nearly equal, since the eclipsing star would move off about as fast as it moved on.

The variation of both these stars is of the same problem. Both stars show variable velocity in the line of sight, and by study of this it has been found that each of them is revolving in a highly eccentric orbit about a dark body—or rather about the common center of gravity of itself and the dark body—in the same period as that of the light-variation. The minimum does not occur when the dark star is between us and the bright one, and so we have additional proof that it is not due to an eclipse. It is also clear that the orbit must be inclined to the line of sight so that the dark star passes to one side of the bright one instead of directly in front of it, as otherwise we should have an eclipse and a second minimum.

The accepted explanation of the variability of these stars is that it is due to tidal action. The attraction of the dark companion must produce enormous tides in the liquid—or, most probably, gaseous—mass of the central star. Owing to the eccentricity of its orbit (which is about the same in both cases under consideration), the least distance of the dark body is but one-third of its greatest, and, since the tide-raising force varies inversely as the cube of the distance, it is 27 times greater at one time than at the other.

As the two bodies approach one another, the increasing disturbance of the atmosphere of the luminous one increases its brightness, the effect reaching its maximum shortly after the passage of the nearest point, or periastron. With the decrease of the tidal force the bright star gradually cools down, rising again only when the return of its satellite stirs up once more its central fires.

#### THE PLANETS.

Mercury is in Gemini, and is evening star till the 12th, when he passes between us and the sun, and becomes morning star. He can only be seen in the last days of the month, just before sunrise.

Venus is evening star, and is gradually coming out from behind the sun into a more conspicuous position, remaining above the horizon more than an hour after sunset.

Mars is evening star, being well past the meridian at sunset. He is more than twice as far from us as he was in February and only about one-sixth as bright, and is still retreating and growing fainter as he moves eastward from Leo into Virgo.

Jupiter is just past opposition, and at his nearest for the year. He is by far the most brilliant object in the southern sky, and his disk and satellites are easily visible with a field-glass.

Saturn is in Sagittarius, close to Jupiter. He is in opposition on the 5th. His rings are seen at the greatest possible angle and form a splendid telescopic sight, in spite of his low altitude.

Uranus is in Scorpio, about 8 degrees northeast of Antares. Neptune is in Gemini, too near the sun to be visible.

Full moon occurs on the morning of the 1st, last quarter on that of the 8th, new moon on that of the 15th, first quarter on the night of the 22d, and full moon once more on that of the 30th. The moon is nearest us on the 11th, and farthest on the 23d.

She is in conjunction with Jupiter on the afternoon of the 1st, Saturn the next morning, Mercury on the 14th, Neptune on the 15th, Venus near moon on the 17th, Mars on the morning of the 21st, Uranus on the night of the 25th, and Jupiter and Saturn once more on the night of the 28th and morning of the 29th.

#### DEATH OF T. C. CLARKE.

Mr. Thomas Curtis Clarke, one of the best-known civil engineers and bridge-builders, died in New York, June 15, in his seventy-fourth year. He was trained to be a civil engineer and early in life engaged in various kinds of railroad work, but finally made bridge engineering a specialty, and his name is identified with many of the most important bridges built in the United States. One of the first of his works in this line was the building of the C., B. & Q. bridge at

Quincy, Ill. In the piers and foundations of this bridge, Mr. Clarke was among the first of American engineers to use concrete upon a large scale. Mr. Clarke was the senior member of the firm which afterward became the Phoenix Bridge Company. Among the famous works on which he was engaged was the erection of the Kinzua Viaduct. In 1884 Mr. Clarke became one of the members of the Union Bridge Company, which soon became the largest concern devoted to bridge-building in the world. While Mr. Clarke was connected with this company they built the famous Hawkesbury Bridge in Australia, which is one of the first cases where a bridge was built in a foreign country by an American concern. He also had special charge of the Poughkeepsie Bridge. It is stated that Mr. Clarke had been concerned in the building of over eighty miles of bridges and viaducts. He was well known as a writer upon professional subjects.

#### SCIENCE NOTES.

The Baldwin-Ziegler polar expedition will start shortly for the north.

Mr. Morris K. Jesup has perfected an arrangement by which the American Museum of Natural History and the South Kensington Museum will exchange exhibits.

The Arnold Arboretum, in the suburbs of Boston, has carried on its highly interesting and important work on a very slender income. Steps are now being taken to raise \$300,000 in addition to the present endowment.

The Massachusetts Institute of Technology has held examinations in London for the entrance of pupils to the Boston institution. The London Engineer says: "It would seem that American competition is not to be confined to commerce in the future."

Prof. Nicols Finsen, the inventor of the light cure for lupus, has been summoned to London by the Queen of England to superintend the administration of the apparatus which her Majesty presented to the London Hospital. The Belgian government also proposes to install the cure at Brussels, and Prof. Dubois has been dispatched to Copenhagen, to become acquainted with its application.

The invention of the mariner's compass by Flavio Gioia is to be celebrated this summer at Amalfi, Italy. Gioia came from Postano in the hills back of Amalfi. There have not been wanting those who contend that the invention, like most others, was gradual, and that the tendency of the magnetized needle to point north was known long before Gioia's time, it even having been familiar to the Chinese.

Prof. Henry Truman Henry Safford, an eminent mathematician and astronomer, died recently at Williamstown, Mass. He was born in 1836 and was known in his early youth as the "Vermont boy calculator." In 1866 he was appointed Director of the Astronomical Observatory at Chicago. From 1869 to 1871 he was engaged upon the great catalogue of stars then in course of preparation by the co-operation of European and American astronomers. This work was interrupted by the Chicago fire of 1871. He prepared a star catalogue which was published by the War Department. He did considerable work in relation to latitude and longitude.

John D. Rockefeller has given \$200,000 to found "The Rockefeller Institution for Medical Research." The gift is not for an endowment fund, but for immediate expenditure. Mr. Rockefeller has for some time been consulting with eminent medical men as to the need of such an institution, and he has had the best of advice. Facilities for original investigation are to be provided, especially in such problems in medicine and hygiene as have a practical bearing on the prevention and treatment of disease. The first work of those connected with the institution will be that of co-operating with the Board of Health in studying its work and the problems confronting it, particularly that of milk supply. Work of a more ambitious nature will be begun in the fall under the guidance of experienced investigators.

In Europe it has been found rather difficult to introduce the circuit-system for the transmission of meteorological messages for a time after each observation. In the United States this is very easily accomplished, but in Europe, where the control of the wires is in the hands of different governments, the difficulty of introducing a similar method is almost unsurmountable. The system recommended by the Deutsche Seewarte is called the radial system, in which the observations pass through the central offices. Special observations have been made for nearly a year at eight A. M. mid-European time, at some thirty-five stations in various countries, including several in the British Isles, and forwarded to the Deutsche Seewarte, which enables the Hamburg office to issue reports as early as nine A. M., and the early publication of this information has been found to lead to such satisfactory results as to warrant a considerable extension of the plan in the near future.

## A NOVEL HOUSE MAIL-BOX.

Our illustration pictures a mail-box which was devised by Mr. Clayton F. Myer, of Silsbee, Tex., for the purpose of facilitating house-to-house delivery and of indicating that mail has been delivered.

The arrangement comprises essentially a box provided with a hinged hood for the letter-receiving slot, which hood when lifted operates a slide by means of chains, to expose the word "Mail," thereby show-



AN IMPROVED MAIL-BOX.

ing that mail of some kind has been delivered. The slide is held in its raised position by a spring, and is restored to its normal position by hand.

The box is also provided with a door through which the mail is removed. The door is controlled from the inside of the house, thereby rendering it impossible to open the box without entering the house. A lock controlled by a shaft holds the door closed. Upon turning the shaft, the door is pressed open by a spring. For the reception of bulky mail, a spring-arm is attached to the bottom of the box. The contrivance is cheap, neat, rain and dirt proof, and secure from thieves.

## CURIOUS DOCKING ACCIDENT.

The illustrations herewith produced give an idea of the accident which recently occurred at Baltimore when the steamship "Hudson" careened while being docked, falling partly upon her side. She was being hauled out on the marine railway at the dock of Messrs. William Skinner & Son, in order to make repairs to a bent propeller blade. The ship was left on the railway with the stern entirely out of water with the exception of about one foot. The work of hauling her out began at high tide, and the after portion of the hull was held in a perpendicular position by driving posts under the rear quarters for shoring. The tide rises and falls about 18 inches at this point, and at low tide so much of the hull was exposed as to overcome, in spite of the supports, the equilibrium of the vessel, and, falling to the left, she struck the side of the dock, breaking down portions of the superstructure. The deck railing was broken and a part of the rigging supporting the masts on the port side was cut away; some of the upper plates in the hull also being bent inboard. Below the water-line the divers found her perfectly tight. The incline of the marine railway is such that, in heeling over, the "Hudson" forced her bows under water to a distance of about fifteen feet from the cut-water.

One of the steamers of the Merritt Wrecking Company was sent for, and the first step toward righting the vessel was to pump out the water which entered the hull through the port windows and forward hatchway. The next step was to stretch cables from the masts and deck stanchions to powerful tugs in the harbor and to the wrecking steamer, and endeavor to pull her out by the bow

into deep water. This failing, weights are to be attached to the starboard side of the vessel, and an attempt will be made to pull her over onto an even keel by a system of cables attached to windlasses connecting with the engine of the marine railway.

Fortunately, the hull of the vessel was empty at the time she was docked; but the work of righting her will, nevertheless, be attended with considerable difficulty, as she is 287 feet in length, 34 feet beam and has a net register of 1,300 tons. She has a cargo capacity for about 2,500 tons of freight and accommodations for sixty passengers. The engines and most of the machinery are located amidship.

## Photographic Printing in Two Colors.

A new method of photographic printing upon paper in two colors has lately been devised by M. Bolle. By this means images may be printed side by side in different colors and an agreeable effect thus produced; it is especially applicable in the case of a central image surrounded by a border of a second color. One of the images is printed from a photographic negative and the second from a negative prepared from a hand design. The method is based upon the combination of the ferro-prussiate (blue print) and the bichromated gum process, and gives a blue image combined with another whose color may be varied according to the taste of the operator. To obtain the blue image the paper is sensitized by a mixture of the two following solutions:

- A. Citrate of iron and ammonia. 15 parts or 15 grains.  
Water ..... 50 parts or 50 minims.
- B. Ferricyanide of potassium. 8 parts or 8 grains.  
Water ..... 40 parts or 40 minims.

These solutions, prepared and filtered, may be mixed in advance and kept in yellow bottles, but it is best to mix at the time of using. The image is strongly printed and developed by washing in water till the whites become pure. The second image may form, for instance, a border for the blue image. To obtain it a plate is first prepared by exposing an ordinary gelatine plate to daylight and developing it until it is entirely black. The design to be reproduced is copied or traced upon tracing paper and transferred to the plate by impression paper. It is then engraved through the film with the point of a needle, giving a negative in black and white. To print this design the border of the blue image is sensitized by brushing over it a thin and even layer of gum arabic, 40 per cent solution, to which is added a sufficient quantity of the color decided upon. When this layer is dry a sensitizing solution of bichromate of potash (10 per cent) is applied in the same way. The printing is carried out as usual and the image developed by



VIEWED FROM THE PORT QUARTER.




STEAMSHIP "HUDSON," CAPSIZED ON A MARINE RAILWAY AT BALTIMORE.

washing in cold or lukewarm water. This process may be modified in different ways and will find many applications; if desired, the center of the image may be printed by the latter method and the margin in blue, or different images may be printed side by side.

## A SELF-CLOSING SPIGOT OR FAUCET.

To provide a means for automatically closing a faucet or tap when a predetermined quantity of liquid has



AN AUTOMATIC FAUCET.

been drawn from a cask is the purpose of a device invented by Mr. David M. Bredin, of Picton, Canada. On the spigot a scale-beam is fulcrumed, the shorter arm of which supports a platform for the vessel to be filled, and the longer arm of which carries a counterpoise which can be shifted. The counterpoise is adjusted at a point determined by the weight of the liquid which is to be drawn from the cask. When the desired amount of liquid has flowed into the vessel, the shorter arm of the scale beam descends automatically, closing the spigot by the operation of a plug. By means of a spring latch the plug is prevented from opening the spigot during the removal of the vessel.

## New Methods of Packing Butter for Shipment.

Our Consul, Mr. Hughes, of Coburg, under date of April 26, 1901, sends the following description of a new method of packing butter for long shipments:

A light wooden case or box is lined thoroughly at the bottom and sides with a layer of plaster of paris one-fourth of an inch thick, on which common glass slabs, with their edges fastened together by gummed paper, so as to make a perfect-fitting box, are placed. In this box the butter is placed, packed in good waterproof paper, in 10-pound packages. The glass top is then put on and sealed carefully with gummed paper bands, so as to make the box air-tight. A one-fourth-inch layer of plaster of paris is then put over this and the wooden cover nailed on. Each of the cases is made to contain about 200 pounds of butter. The plaster of paris being a non-conductor, very little heat reaches the butter, which arrives at its destination in good condition. The Consul is informed that very successful results have been obtained by shipping butter packed in this manner from Melbourne to Kimberley—rather a severe test.

The Diatto surface-contact system does not appear to be working very successfully in Paris. There have been so many accidents and breakdowns that a committee was appointed to inquire into the trouble, and it reported that the damage was due to several causes. First, insufficient drainage of the surface-contacts and conduits, causing shunt currents; second, to unsatisfactory insulation; third, to a deposit of carbon caused by sparking; fourth, bad insulation of the cables.



## THE WATER SUPPLY SYSTEM OF CHICAGO.

BY F. B. ENDREKE.

It is not yet three-quarters of a century (November 10, 1834) since the Board of Trustees of the infant Chicago paid \$95.50 for the digging of a well as a



THE INTAKE CRIB COMPLETED.

means of water supply. Outgrowing that, in January, 1836, the Chicago Hydraulic Company was incorporated by the State Legislature and given a charter which was to continue in force for seventy years, by the provisions of which lake water was to be furnished to Chicago. The works of this company were put in operation in the spring of 1842. They comprised a reservoir, about two miles of wood pipe and a 25 H. P. engine, the whole costing about \$24,000.

This company, however, supplied only a portion of the south and west divisions of Chicago, and did not reach the north division at all. The inhabitants of the unsupplied sections were furnished with water either from the river, or by the "water-cart system" from the lake. Finally it became clear that the whole water supply needed to be managed by the city, and compromises having been agreed upon between the company and the city in 1852, the latter put its works into operation immediately.

The north side pumping station at the foot of Chicago Avenue was the first station to be established. It began work in December, 1853, with a capacity of 8,000,000 gallons every twenty-four hours. The water came from an inlet basin on the lake shore cut off from the lake by a semi-circular breakwater with an opening to the southeast. There were three reservoirs holding from two to three days' supply. They were at LaSalle and Adams Streets, Chicago Avenue and Sedgwick Street, and Monroe and Morgan Streets. The first iron distribution pipe, 4 inches in diameter, was laid in 1852. In 1887 a shore-inlet tunnel 7 feet in diameter and 1,500 feet long, with an inlet shaft protected by a crib opposite to the north side station, was completed

for use when the supply was endangered by ice, or from any other cause, at the two-mile crib. The addition of needed engines and other facilities to the north side station has kept this, the oldest and largest station in the city, in efficient use up to the present time. In 1869 the greater part of the station as it is to-day was finished. The style of architecture is castellated Gothic with heavy battlemented corners, executed with solid, rock-faced, ashlar stone and cut trimmings, with details of a massive and permanent character. The tower is the most imposing feature of the structure, and in the days preceding the sky-scraper epoch, a view of the lake and city from its top was thought to be very fine. A new lake tunnel, 7 feet interior diameter, extending from the crib to the north side station, was finished July 3, 1874, and in October of the same year it was extended under the land to the new pumping station at Ashland Avenue and Twenty-second Street (the west side station).


On November 6, 1876, the year in which the "Board of Public Works" was succeeded by the "Department of Public Works," with a single responsible head, the west side pumping station was put in operation, its capacity being 30,000,000 gallons per day. In 1884 this was raised to 60,000,000 by the addition of two new engines. The growth of the city's needs and the constant outlay necessary to satisfy them may be seen when this amount is compared with that actually pumped at this station for



INTERIOR OF THE CRIB.

the year 1899, the amount reaching the enormous output of 19,281,301,400 gallons. It will be remembered that the first inlet basin to supply Chicago with water was quite near the shore, and although the city grew rapidly and packing houses and distilleries added their refuse to the Chicago River, and complaint was made by the citizens that the source of their water supply had become contaminated, no effort toward change was made until 1861, when the Board of Public Works entered upon its duties. A plan of filtration was first experimented with, but it was soon cast aside as impracticable, and it was decided to construct a tunnel, which would bring lake water from a distance sufficiently removed from the contaminating river deposits to insure its purity. It was thought that this could be accomplished by using a tunnel two miles in length. The horizontal diameter of the tunnel was fixed at 5 feet, that also offering a capacity sufficient to furnish 50 gallons of water per day to each person in a population of one million. Work was begun on this tunnel March 17, 1864, the introduction of pure lake water into the finished waterway being celebrated with appropriate public ceremonies March 25, 1867.

The present system of water pipe tunnels under the Chicago River was not originated until 1869. An accident occurred August 13 of that year, in which the water main crossing the river at Chicago Avenue was broken by the dragging anchor of a vessel, and the west side thereby deprived of water for



THE FOURTEENTH STREET PUMPING STATION.



NORTHEAST LAKE TUNNEL—INTAKE CRIB DURING PROCESS OF ERECTION—THE PARAPET.



NORTHEAST LAKE TUNNEL—INTERNAL DIAMETER 10 FEET.

three days. This brought out the necessity of tunnels under the river bed. Up to this time all pipes at intersections of the river had been laid on the river bottom. But the pollution of the water continued, and when the construction of the next tunnel was planned, in 1887, it was decided to make it 8 feet in diameter and to extend it four miles into the lake. The initial work was done in the same year on a shore shaft at the foot of Peck Court. The land ramifications connecting the shore shaft with the south side and central stations were nearly completed in 1888, but it was not until December 15, 1894, that the immense work, up to that time the greatest engineering enterprise undertaken by the city, was completed. The interdependence of pumping stations and feeding tunnels prevented the central pumping station at Harrison Street from doing full work before the four-mile tunnel was in operation, although it began service July 14, 1890. The Fourteenth Street station was built in 1890, and re-equipped in 1898.

But increased as were the facilities for water supply, the growth of Chicago afforded no chance for a breathing spell for the water supply department. July 15, 1889, the suburban towns of Hyde Park, Lake, Jefferson, and Lake View were annexed to Chicago, adding to its population 220,000 souls, and to its water works system the pumping stations of Sixty-eighth Street and of Lake View; one lake tunnel 6 feet in diameter and 8,000 feet long with a submerged inlet for Hyde Park and Town of Lake; one lake tunnel in process of construction, 6 feet in diameter, for Lake View and Jefferson, and about 350 miles of water pipe. Immediate extensions and repairs for the adequate water supply of this new territory were imperative. The original plans of the Lake View water department contemplated a tunnel 6 feet in diameter extending easterly from the foot of Sulzer Street to a point one mile from shore. After annexation and while the work was in progress, it was decided to extend the tunnel a mile further. In order to utilize the construction as soon as possible a temporary crib was sunk 6,000 feet from shore on the line of the tunnel and water obtained from this point, work meanwhile progressing from a temporary shaft to the outer or permanent in-take crib previously sunk. This tunnel was completed in July, 1896, and the intermediate crib abandoned and finally removed in 1899. The construction, appointment, and furnishing of the Carter H. Harrison crib mark it as the most modern and efficient of the Chicago cribs. Its cost, including substructure, superstructure, and landing, was \$192,441.40.

In 1895 it was again found necessary to plan for the construction of two additional pumping stations to relieve the sufferings of the remote west and north-west sections of the city due to an inadequate water supply. As a feeder for these, it then became necessary to build a new lake tunnel, which is divided into a lake section and three other sections covering the land ramifications. The lake tunnel extends to the Carter H. Harrison crib, and was completed in January, 1899. Section one of the land tunnel was completed in 1897, number two and number three in 1900. The capacity of the lake tunnel is 200,000,000 gallons per 24 hours, and the cost of the new service was \$4,986,266.37. With the completion of the new tunnels and pumping stations a population of 3,500,000 can be supplied with 150 gallons of water per day to each person, and there will still be ample reserve machinery.

#### PROVISIONING A TRANSATLANTIC LINER.

Not by any means the least impressive evidence of the huge size to which the modern transatlantic steamship has grown is to be found in the graphic representation, on the front page of this issue, of the bewildering amount of provisions that have to be taken aboard for a single trip across the ocean. A mere tabulation of the various kinds of food which go to replenish the ship's larder, during the few days which she spends in port, fails to convey any adequate idea of the vast amount of stores taken aboard. Our pictorial representation is, of course, purely imaginary, particularly as regards the live stock; the beef, mutton, game, etc., being received on the ship in the dressed condition, no live stock whatever being carried. The drawing was made up from a list of the actual amount of provisions carried on a recent eastward trip on the Hamburg-American liner "Deutschland," and the number of live stock which contributed to meet the supplies for one voyage was estimated from the actual number of cattle, sheep, etc., that would be required to make up the total weights in dressed meats given in the table. With the exception of the live stock, the provisions are shown in the actual shape in which they would be taken on board.

The dimensions of the vessel are: Length, 686 feet; beam, 67 feet, and displacement, 23,000 tons; her highest average speed for the whole trip is 23.36 knots, and she has made the journey from Sandy Hook to the Lizard in five days, seven hours and thirty-eight minutes. In considering the question of feeding the pas-

sengers on a vessel of this size, the thought is suggested that there are other hungry mouths within the hull of the ship besides those to be found in the dining saloons of the passengers and the messrooms of the crew; mouths that are so voracious that they require feeding not merely at the three regular meal hours of the ship, but every hour of the day and night, from the time the moorings are cast off at one port until the vessel is warped alongside at the other. We refer to the 112 furnaces in which the fuel of the sixteen boilers in the boiler-room is consumed at the rate of 572 tons per day. Now, although the voyage from New York to Hamburg lasts only six or seven days, according to the state of the weather, the bunkers of the ship are constructed to hold a sufficiently large reserve of coal to cover all contingencies, her total coal capacity being about 5,000 tons; and at each voyage care is taken to see that they are pretty well filled.

The total number of souls on board of the vessel when she has a full passenger list is 1,617, made up of 467 first cabin, 300 second cabin, 300 steerage and a crew of 550, the crew comprising officers, seamen, stewards and the engine-room force. Sixteen hundred and seventeen souls would constitute the total inhabitants of many an American community that dignifies itself with the name of "city," and it is a fact that the long procession which is shown in our illustration, wending its way through the assembled provisions on the quay, by no means represents the length of the line were the passengers and crew strung out along Broadway or any great thoroughfare of this city. If this number of people were to march four deep through Broadway, with a distance of say about a yard between ranks, they would extend for about a quarter of a mile, or say the length of four city blocks.

To feed these people for a period of six days requires, in meat alone, the equivalent of fourteen steers, ten calves, twenty-nine sheep, twenty-six lambs, and nine hogs. If the flocks of chickens, geese and game required to furnish the three tons of poultry and game that are consumed were to join in the procession aboard the vessel, they would constitute a contingent by themselves not less than 1,500 strong. The ship's larder is also stocked with 1,700 pounds of fish, 400 pounds of tongues, sweetbreads, etc., 1,700 dozen eggs and 14 barrels of oysters and clams. The 1,700 dozen of eggs packed in cases would cover a considerable area, as shown in our engraving, while the 1,000 bricks of ice cream would require 100 tubs to hold them. Of table butter there would be taken on board 1,300 pounds, while the 2,200 quarts of milk would require 64 cans to hold it, and the 300 quarts of cream 8 cans.

In the way of vegetables there are shipped on board 175 barrels of potatoes, 75 barrels of assorted vegetables, 20 crates of tomatoes and table celery, 200 dozen lettuce; while the requirements of dessert alone would call for  $4\frac{1}{4}$  tons of assorted fresh fruits. For making up into the daily supply of bread, biscuits, cakes, pies, and the toothsome odds-and-ends of the pastry cook's art, there are taken on board at each trip 90 barrels of flour, each weighing 195 pounds, this item alone adding a weight of  $8\frac{1}{2}$  tons to the cooks' stores. To this also we must add 350 pounds of yeast and 600 pounds of oatmeal and hominy.

Under the head of liquids the most important item is the 400 tons of drinking water, whose bulk is adequately represented by the circular tank shown in our engraving. This is supplemented by 12,000 quarts of wine and liquors, 15,000 quarts of beer in kegs, besides 3,000 bottles of beer. Last, but not by any means least, is the supply of 40 tons of ice.

Of course, it will be understood that, as in the case of the coal, it is not to be supposed that all of this supply will be consumed on the voyage. There must be a margin, and a fairly liberal margin, of every kind of provision. Moreover, the extent to which the larder and cellar are emptied will vary according to the conditions of the voyage. In tempestuous weather, where the trip is a succession of heavy gales, and the dining room tables are liable to be practically deserted for two or three days at a stretch, the consumption will be modified considerably. Stormy voyages of this character, after all, occur at infrequent intervals, and as a rule the supplies are pretty well consumed by the time the passage is over.

#### Fire from Waste Paper.

The deterioration in the quality of paper increases the liability of fire wherever waste paper is accumulated in any quantity. Most modern paper is made from wood and other vegetable fibers which, chemically, are not very different from the component material of a haystack. If the waste paper is stacked in large quantities, and especially if it happens to be a little damp, heating takes place just as with a prematurely stacked haystack, and spontaneous combustion may at any time break out in flame, as it has often been known to do in the farmyard, and of late years the greatest care and vigilance has been necessary to guard against it.

#### Engineering Notes.

Ten American locomotives have just been delivered to the Paris-Lyons Railway.

Acetylene black produced from the carbon of acetylene is of excellent quality, fineness and purity. By reason of its very fine division acetylene black seems particularly suited for the production of India ink.

During the year 1900 the shortest passage of a sailing ship from London to Calcutta was 82 days, and the longest 199 days. The shortest passage from London to San Francisco was 109 days, and the longest 203 days. The shortest trip from San Francisco to London was 96 days, and the longest 181 days.

A new solder is being introduced by an English concern. It consists of an alloy composed of pure metals mixed in the most efficient proportion, and incorporated with it is the necessary amount of rosin. The solder is made in the form of a tube with a narrow bore, the central cavity being occupied by the flux.

We learn from The Engineer that railway unpunctuality is by no means unknown in Russia. On the Vistula line in 1900, out of 348,933 trains which were run, 52,020, or 15 per cent, left the station before time; 74,909, or 21 per cent, arrived late. The other lines have not much more to boast of. The only fairly punctual line is the Warsaw-St. Petersburg one, on which only 7 per cent of the trains were late.

Arrangements are in progress for the visit of a representative commission of British artisans to this country. It will be their business to make a tour of observation among our varied industries. The commission has been organized through the medium of a London weekly called "Red Letter." The men are elected by popular vote. Their itinerary will include a visit to the Pan-American Exposition.

When the British Chancellor of the Exchequer levied the tariff of twenty-five cents upon each exported ton of coal, it was maintained by the various colliery owners that a heavy blow had been dealt to the English industry. As a matter of fact, however, since the duty was imposed the exports of coal from Great Britain have increased considerably, especially to Germany and France. During the month of April 620,000 tons of coal were shipped to France, while the quantity for the first four months of the present year aggregates 1,882,880 tons, representing a value of \$7,737,400. The shipments to other parts of the Continent have been equally heavy.

A Baltic-White Sea Canal is proposed in order to more rapidly develop the vast territory of Archangel. It is contemplated to build the canal large enough to admit vessels of ocean tonnage. The canal would also be of great value to the Russian navy in time of war. If it is carried out, the total length of the canal will be 598 miles; 304 miles of the route will be formed by lakes. The canal will follow the bed of the Neva as far as St. Petersburg, crossing Lake Ladoga and following the Svir, which unites Lakes Ladoga and Onega. Different watercourses will then be utilized, the channels being enlarged and deepened until the White Sea is reached at Soroskaya. It is estimated that the work can be completed within a year, and that the cost would be \$10,300,000.

A scheme for supplying the manufacturing districts of South Staffordshire with gas made by the patent Mond process is being considered by the British government. The gas is not to be employed for illuminating purposes, but is to be devoted to heating and manufacturing requirements entirely. The Mond gas is manufactured from an inferior quality of coal at a very cheap rate. The President of the Society of Chemical Industry of Great Britain, who is interested in the scheme, stated before the Parliamentary Committee that whereas now 50,000,000 tons of coal are annually consumed for manufacturing purposes in this district, the necessary steam and motive power will be obtained from Mond gas distilled from 10,000,000 tons of coal, thus effecting a considerable economy in the consumption of coal. The gas is to be supplied at the low price of four cents per 1,000 cubic feet.

Two derailments which have occurred recently on the Siberian Railway are a further proof, if any were needed, that the line has been too lightly constructed to enable it to carry the heavy locomotives now running on it, to say nothing of the ever-increasing freight traffic. The first derailment referred to was caused by a "burst rail," and, of course, until the entire line has been relaid with heavier and sounder rails, there will be always the risk of other "burst rails," causing loss of life and interruption of the traffic, says The Engineer. The second accident, which is the fifth of this nature on the new line, shows that the supervision exercised over the traffic is far too weak. The control of the line is in the hands of one man. Both the people and the press of Siberia have come to the conclusion that to insure the proper working of the line in the best interests of the country, the Siberian Railway ought to be divided into three or four separate and independent sections.



## Correspondence.

Photographing in the 50,000th Part of a Second.  
To the Editor of the SCIENTIFIC AMERICAN:

In the article appertaining to the history of photography for the past fifty years, published in Sunday's Sun, May 19, 1901, by George G. Rockwood, mention is made of the fact of his having taken photographs in the twenty-four thousandth part of a second, by means of the discharge from a Leyden battery.

As the writer conducted the electrical part of the experiments referred to, and still retains the original apparatus used for the purpose, as well as data relating to the experiments made first at Mr. Rockwood's laboratory, in Union Square, then in the basement of Kurtz's studio—opposite the Post Office at that time—and later at the residence of W. E. Crampton, in Brooklyn, it may add to the history, in a more detailed manner, of this particular line of photography, if the following facts relative to the subject are brought forward.

It was at the suggestion of the late Josiah P. Fitch, a then well-known patent lawyer of New York, that the question as to whether it was possible to have plates made sensitive enough to receive impressions during the minute period of a Leyden battery discharge came up.

Mr. Rockwood was consulted, but, of course, could not guarantee that his plates would respond during the infinitesimal fraction of a second that the Leyden spark gave light.

However, he prepared a number of special plates, and one evening during the summer of 1881 an electro-static machine of French make, giving a spark, under favorable conditions, of eight inches, a battery of fifteen Leyden jars and the necessary mechanical and telephonic apparatus were set up and ready for use about 10 P. M.

A number of scientific men were present, one of whom would be talking in the transmitter, upon the contacts of which the camera was focused, while another would listen at the receiver, in a different apartment, and record the messages articulately received.

Mr. Rockwood figured the duration of the electric spark on the basis of Wheatstone's calculation, that a spark passing through a space of one inch and having the electro-motive force behind of ten Leyden jars would pass in the 24,000th part of a second.

As the electro-motive force of the spark used in these experiments was the product of fifteen jars, connected in series, and the space traversed was from one-quarter to three-eighths of an inch, the duration of the spark, according to the above calculations, was in the vicinity of the 50,000th part of a second instead of the 24,000th.

There was an anxious time spent while Mr. Rockwood was developing the first half dozen plates, as in case of their showing nothing, it would be useless to proceed further in that line of demonstration.

To the surprise, and gratification, of all, the photographs of the transmitter vibrating point came out as clear and distinct as if the exposure had been for a second instead of the 50,000th part of one, and many other fine impressions were taken that evening.

The stationary transmitter contact consisted of a half-inch length of carbon one sixty-fourth of an inch in diameter, and the vibrating one, of a platinum wire of the same dimensions, but tapering to a fine needle point where it contacted with the carbon.

The Leyden spark was discharged at a distance of one inch from the transmitter contacts, on the opposite side of which the camera was focused so as to be in a direct line with them and the center of the space over which the discharge took place.

Some of the photographs were taken with the jars connected in multiple and in multiple-series, but the best results were obtained when all were connected in series. Five of the jars were fractured, through the chains being too short to rest on the inner tin foil.

On examining the fractures with a microscope, they presented a funnel-like formation and had the appearance of being fused, a very surprising fact considering the enormous speed with which the sparks passed through the glass. One of the holes had the appearance of having been made by a bullet.

While the experiments were being conducted the laboratory was in absolute darkness, and the sensations experienced by those present when the discharge took place were of a very peculiar nature, especially when anyone, accidentally, got too close to the Leyden jars. Often, when seemingly safe for handling, a residual charge would assert itself to someone's discomfort.

Among those present were Josiah P. Fitch, W. E. Crampton and T. A. Richards, M.E.

Subsequently to the above experiments, several nights in Mr. Kurtz's studio resulted in the production of many plates of varying quality.

It was then decided that micro-photography would be necessary for the proper elucidation of the object aimed at, and Mr. Crampton immediately had a room

equipped for the purpose in Brooklyn, and went thoroughly into the study of rapid photography.

A very powerful microscope was attached to the camera used, and necessitated the use of very minute contact points on the transmitter, as it had to be brought to within the thickness of a piece of cardboard from the lens, to get the proper focus, and the handling of the apparatus had to be conducted with extreme delicacy and care, through one of the contacts being made from a piece of carbon filament taken from an incandescent lamp and the other from a very fine platinum needle.

The minute contact points were magnified to about one inch in diameter and showed results far ahead of the previous experiments, and seldom were the points caught in actual contact.

By several months' hard work, a beautiful collection of negatives was obtained, showing the contacts at varying positions relative to each other, every negative being taken while articulate speech was being transmitted and received over the telephone.

Those experiments showed visually and conclusively that mechanical contact could be and was broken to a minute extent between the transmitter contacts, while articulate speech was being transmitted, and without impairment of its quality, but, of course, the Bell telephone people argued that it was not by reason of, but in spite of, the mechanical breaks that speech was transmitted, and if the quality of speech was not impaired it was for the reason that, although the circuit might be broken mechanically, it was closed electrically, through the current bridging the gap.

There is little doubt but that Mr. Rockwood is entitled to the credit of making the first photographs by means of a spark from a Leyden battery, and that Mr. Crampton was the first to make micro-photographs by similar means. The same electrical apparatus was used in both cases.

After going the length he did, Mr. Crampton decided to have made the most powerful microscope that could be focused on the transmitter contacts, and use it for the purpose of examining with the eye the actions that took place between them. The microscope was of 4,000 diameters and the contacts had to be flattened to allow of its being brought within range. It was rigidly fastened to the same base as that of the transmitter, but even then, owing to its great magnifying power, the least touch would throw it out of focus, and it required a great deal of perseverance and skill to use it at all.

A minute incandescent lamp was placed behind the contacts, and when speech was being transmitted the vibrations were too rapid for the eye to catch the contacts together, a thin streak of light appearing between them, all the time that speech was being transmitted.

When the incandescent lamp was extinguished a most beautiful halo of bluish, purple light, radiating from the points, was seen. Magnified as it was, it seemed to extend about half an inch around the contacts, melting into the darkness in a very gradual and misty manner, that would seem to confirm the theory of some experts that a luminiferous ether conducted the current when the points were separated. These effects could, of course, not be distinguished with an ordinarily powerful microscope.

J. HARI ROBERTSON.

Brooklyn, N. Y.

## The Nernst Arc Light.

Somewhat more than a year ago the Nernst incandescent lamp was brought forward with a filament of refractory, earthy material instead of the usual carbon, and heated in the open air instead of in a vacuum. In the *Elektrotechnische Zeitschrift* of February 14 an arc lamp with pencils of similar refractory material is described. This new electric arc is similar to the Jablockhoff candle of long ago, in that the arc length from point to point of the electrodes for the case reported is about 0.04 inch and nearly constant. The most important feature reported for this new arc is its comparatively high efficiency. Good incandescent lamps with carbon filaments show an efficiency of 3 watts per mean spherical candle power. Open-arc direct current lamps show an efficiency of about 0.3 watt per candle power in the direction of greatest intensity of light, but this rises to about 0.6 watt per mean spherical candle power. This great variation between mean and maximum candle power is partly due to the shape of the carbon points, which form so as to produce the greatest illumination at an angle of about 45 degrees below the horizontal. The new arc lamp above mentioned is reported to have given a horizontal candle power of 556 units with an expenditure of 154 watts at the arc. This corresponds to a horizontal illumination of 0.27 watt per candle, or about that of present direct current arcs at 45 degrees below the horizontal. While the ordinary arc is maintained between carbon points, one of which is convex and the other concave, this new arc takes place between points of refractory material, both of which are convex. Moreover, the pen-

cils of refractory material for this latter arc are only 2.5 times as great in diameter as is the arc length, while the diameter of carbon points is generally as much as six times the lengths of their arcs. These conditions make it appear that the arc with pencils of refractory material may have a much wider field of maximum illumination than does the direct current arc with carbon points, and consequently that the mean spherical candle power of the new arc may be nearer that at the horizontal or maximum point than is the case with carbons and direct current. With alternating current the mean spherical candle power of the arc between carbons of convex points is about 70 per cent of the maximum intensity. If this relation holds good for the new lamp, its mean horizontal candle power for the case reported should be  $556 \times 0.7 = 389.2$  units, and the efficiency  $154 \div 389 = 0.4$  watt per mean spherical candle power. Another important feature of the new lamp seems to be its adaptation to moderate rates of watt consumption and candle powers, because of its simplicity. The considerable amount of mechanism incident to the arc of varying length in a lamp with carbon points, and the lower efficiency of very small lamps of this kind, has tended to confine their use to points where large candle powers are desired. A. D. A.

## Automobile News.

Motor carriages are possessed by King Edward VII., by Queen Alexandra, the Czar, the Emperor of Germany, the King of Belgium, the King of Italy and the Shah of Persia. Queen Alexandra uses an electric motor car.

Automobile omnibuses are to be run between Huntington, Northport and Oyster Bay, L. I. They will carry fourteen to eighteen passengers. The steering is done by means of compressed air. Both power and hand brakes are used. The motor is of sixteen horse power.

According to The Automobile Magazine, when a horse has been injured in the steeplechases at Auteuil, France, and is unable to rise, a specially constructed motor car is brought up and the wounded animal deposited in it and transported away to the care of the veterinary surgeon.

A novel type of motor war machine is being built by Vickers, Sons & Maxim, Limited. It is an armored car intended for the protection and inspection of railways. It runs on the rails and is propelled by a petrol motor, the armament consisting of a one-pounder Maxim gun. Each machine is constructed to be manned by one officer and two or three men.

The Fifth Avenue stages of New York city are all to be operated by electricity. The development of the electric omnibus has been long delayed by the difficulty of finding a satisfactory storage battery. The new vehicles which have been ordered will be ready about August 1, and they will be capable of holding thirty-four persons. The top of the old stages were so low that they were uncomfortable for tall persons. This defect has been remedied in the new ones. They will be double-decked affairs and will be equipped with rubber tires.

## Observations of the Giacobini Comet—Nice Observatory.

M. Perrotin has communicated to the Académie des Sciences a series of observations made upon the comet discovered by M. Giacobini at the Nice Observatory on the 20th of last December. These observations, which were made at Nice from the 24th of December to the 11th of January, are shown in the table.

APPARENT POSITIONS OF THE COMET.

Date.	Mean Time of Nix.	$\alpha$	$\delta$
December 24	7 h. 38 m. 25 s.	22 h. 57 m. 19.60 s.	112° 49' 12.5"
December 25	9 34 50	23 0 22.50	112 49 30.5
December 26	7 49 38	23 0 28.06	112 55 39.6
January 6	6 36 19	0 13 5.98	113 7 39.3
January 11	6 51 8	0 40 10.40	113 40 58.2

These observations do not as yet advance very much farther the present knowledge of the orbit, whose parabolic elements were at first calculated by Messrs. Kreutz and Möller, of the Kiel Observatory, and later by Mr. Campbell, of Mt. Hamilton, but since the recent atmospheric troubles the heavens have again become clear, and the observations will be taken up again with the hope of making new calculations. This comet is likely to be of especial interest, owing to its direct movement and the value of certain of its elements, which make it resemble a singular type of comets whose number is continually increasing. M. Perrotin thinks that we shall soon be edified upon this point if the new body, whose brilliancy is decreasing, may be followed long enough to permit the determination of elements having for base an arc of some extent. The tail of the comet extends at an angle of position near 45 degrees, and measures from 2 to 3 minutes of arc in length; the nebulousity of the head, which is regularly rounded, surrounds a well-characterized nucleus of about the 11th magnitude.

## THE GANZ ELECTRIC LINE OF VALTELLINA.

In a very short time the electric line of Valtellina built by Messrs. Ganz & Co., of Budapest, will be opened to the public. The line has attracted no little attention among European electrical engineers, for the reason that it represents the very highest development of the Ganz three-phase high-tension system of electric traction.

The Valtellina line is some 60 kilometers, or 38 miles in extent. Starting from Milan, it runs to Lecco, at the south-east corner of Lake Como, extends along the eastern shore to Colico, at the north end, and then branches off to Chiavenna on the north and to Sondrio on the east. The high-tension lines deliver the primary current of 20,000 volts to nine stationary transformers, which feed the current to the trolley wires and earth rail as three-phase current at 3,000 volts. The efficiency of transmission from the dynamo to the transformers averages 95 at full, 94 at the half, and 94 per cent at quarter load. Current is generated at a central station situated at Morbegno, between the Colico-Sondrio branch. Hydraulic power is used to develop electrical energy. Three turbines, each of 2,000 horse power, are directly coupled with three-phase generators, which supply the primary current of 20,000 volts.

For the line at Lake Como the motor cars are 18.1 meters in the carriage body and 19 meters (62½ feet) over the buffers. The cars rest on two bogie-trucks, each truck having a wheel-base of 2½ meters. Without passengers a car weighs 50 tons, including the motors. The wheels are 1.17 meters in diameter, while those of the electric freight locomotives supplied to the same line have a diameter of 1.4 meters. The locomotive motor weighs 3.8 tons; its rotor about 1½ tons. The car-motors with a smaller size wheel weigh 3½ tons approximately. Each cascade pair of these motors develops a full-load horse power of 150, while the high tension motor itself, when running at full speed with the low tension motor cut out, yields about the same horse power. Thus, 300 horse power are developed in one truck carrying two pairs of motors, or 600 horse power (450 kilowatts) on one train with front and rear driving cars.

The current generated at the central station has a frequency of 15 per second. When running synchronously the high tension motors make 300 revolutions per minute. In the rotor of the same motor the periodicity of the induced currents varies according to the slip. During the start, when the high tension is switched into cas-

cade connection with the low tension motor, after the speed has risen to "half speed," or 150 revolutions per minute—above which speed the cascade connec-

passengers and freight. Passengers will be carried by the cars at a speed of 60 kilometers (37½ miles) per hour. The electric locomotives will be used

for hauling freight trains. Each train will have a net weight of 250 to 300 tons. The speed to be attained will be about 30 kilometers (18½ miles) per hour.

The commercial merits of the system are many. The initial outlay is not inordinate. The annual cost of maintenance is said to be comparatively small. For railways of considerable length and heavy traffic,

less maximum power is required in the central station with the Ganz high tension distribution than with the necessarily low tension of continuous current distribution, the ratio of maximum to average load at the central station being less.

The electrical merits of the system are no less noteworthy, especially when the length of transmission from one central station is considered. By reason of the high voltage no large currents are used. The loss involved in converting to continuous current by rotary converters is eliminated. The use of pure induction motors without commutators, and the coupling of these in cascade pairs, results in a high motor efficiency.

## Our Mineral Resources.

A chart published by the Geological Survey gives a summary of the mineral products of the United States for the past ten years, says Bradstreet's. The aggregate values have increased by more than one-half in that period, and the figures for 1899 are greater than in any previous year, footing up the enormous total of \$976,000,000. The value of the metallic products of the year is given at \$527,218,084 and of the non-metallic at \$447,790,862. The latter class includes, of course, the coals—\$168,000,000 in bituminous and \$88,000,000 in Pennsylvania anthracite—\$64,600,000 in petroleum, \$20,000,000 worth of natural gas and large value in stone, brick clay and cement, with various other minerals. Of the metals, our pig iron is worth almost as much as all others together, the value of the product in 1899 being given at \$245,000,000. Copper comes next with \$104,000,000, and the \$71,000,000 in gold is third. The market value of the silver produced in 1899 was about \$33,000,000 and the lead and zinc together were worth about as much. Quick-silver, aluminium, antimony, nickel and platinum are the other metals that figure in the table.

Applied on a burn, where the skin is not yet open, turpentine quickly alleviates the pain.



THE GANZ EXPERIMENTAL ROAD ON ALTOPEN ISLAND, NEAR BUDAPEST.




DUMMY CAR OF THE GANZ EXPERIMENTAL ROAD.




INTERIOR OF CAR ON GANZ VALTELLINA ROAD.

locomotive motors is 125 revolutions per minute. The Valtellina locomotive motors are not geared in cascade; they are all high tension.


The line will be used for the transportation of both



ELECTRIC FREIGHT LOCOMOTIVE FOR THE VALTELLINA ROAD.



GANZ ELECTRIC CAR FOR THE VALTELLINA ROAD.



TRUCK OF A VALTELLINA CAR.



## METHOD OF UTILIZING OLD STREET CARS.

It was reserved for some original genius in San Francisco to discover a method for the utilization of ancient and out-of-date street cars. There was once a limited demand for these articles from young and ambitious communities that wanted to inaugurate a street railway system of their own and were willing to buy rolling stock, even second-hand, provided the cost was low enough, but the change in the metropolitan systems, first from horse or mule power to cable roads, and afterward to the employment of electricity as the motive power, together with a general demand from the public for improved cars, left so large a number of the old-fashioned kind on hand that the companies were at a loss what use to make of them. To break them up into firewood seemed to be the only disposition possible. The supply was infinitely greater than the demand.

An Italian immigrant in San Francisco solved the problem. He had purchased a lot of land, but had no money left with which to build a dwelling. Observing several of the old cars in store he bought one for \$10 and had it transported to his land, where, at small cost,

angles, and plank walks are laid so as to give pedestrians access to their homes without wading through the deep sands. Few of these cars have been adorned with a coat of paint. The exteriors are generally intact, and the conspicuous signs denoting the route over which the cars once perambulated are not obliterated.

Some methods are used in the adornment of these curious resorts. Many of them are covered with vines, most have galleries extending around the front and sides. The roofs of some are arranged as lookouts, and awnings drop over the windows. There is considerable space for storage below the cars, while other cars acquire additional room by little extensions. In some instances one car is raised above another, and sometimes the cars are laid upon other buildings, thus giving an extra story. The platforms of the cars are often transformed into balconies and bay windows with the aid of the carpenter and glass fitter, and afford points of observation protected from the cold winds, besides giving extended views of sea and land.

The arrangement of the interiors of these dwellings is highly ingenious, the necessities of the case requir-

## Electric Motors for Street Cars.


Three methods of supply for motors driving electric street cars are now in vogue, two being practised in the United States, while the third is found in Europe. The most common arrangement includes direct current generators at the main station, operating at 500 to 600 volts, distribution lines leading from these generators to the trolley lines, and direct current car motors. Another plan, of which an example is found in New York city, provides only alternating generators of comparatively high voltages, as 6,500 or more, at the main station, lines that connect these generators with transformers at sub-stations, rotary converters fed from these transformers and developing direct current at 500 to 600 volts, and lines that distribute this last current to the trolley and direct car motors. The third system, examples of which can be found by crossing the Atlantic, avoids the use of sub-stations and their rotary converters, and connects high tension alternating generators at the main station to transformers on the moving cars, by means of the necessary lines and trolleys. On the electric cars the transformers reduce the high line pressures



A "Cartown" Home.



"Cartown," San Francisco.



A "Cartown" Skyscraper.



Interior of a Car Home.

## CURIOUS VILLAGE IN CALIFORNIA, BUILT OF OBSOLETE STREET CARS.

he built a small addition to it and provided a very comfortable home for the family. This example was followed by others, and in various parts of San Francisco there may be found discarded street cars doing duty as dwellings, barns, wood and outhouses that are not only substantial, but at the same time economical and highly picturesque.

There is a little settlement just outside the city where the large majority of the structures were once street cars. It is located at the ocean beach on the shore end of Golden Gate park. What community of interest prompted the beginning of this unique settlement is not known. The fact that the lands are of small value and not likely to be acquired for public uses in many years probably had its influence, though the situation, close to the resounding ocean and bordering upon a largely frequented boulevard, had attractions for many. There are perhaps fifty of these car dwellings in the little settlement, many of them fitted out with considerable elegance and numerous conveniences. They are arranged upon a general plan affording their occupants the widest views, all fronting the sea. Streets intersect, at right

ing the utmost economy of space, the average sleeping car suggesting a model. Half a dozen persons have been at night accommodated with lodgings in one of them. Ventilation is always assured.

While there are many families permanent residents of "Cartown," the larger number occupy the "vehicles" as others do the house-boat, giving opportunities for original methods of entertainment and diversion for themselves and friends. Confined and restricted as these dwellings are, there is compensation in the fresh ocean breezes which here blow right from the sea, besides the enjoyment of a health-giving environment. History and romance have been ransacked in providing names for these car "villas" suitable to the facetious idiosyncrasies of their various owners. In "Cartown" the "Villa Miramar" and "Château Navarre" adjoin the modest restaurant and more conspicuous bar.

There are many kinds of trades pursued in this odd settlement, restaurants and bars being most numerous. "Cartown" is an interesting spot for the visitor, not only on account of its individual attractions, but as a demonstration of the problem of what can be done with street cars that have outlived their usefulness.

to those suitable for alternating three-phase motors, which are used to supply the required power. This last system has the obvious advantage that it avoids the expense of sub-stations, rotary converters, and 500-volt distribution lines incident to the second system named. To offset this advantage, the three-phase motor is not yet as desirable in efficiency and regulation as its direct current competitor. The alternating, long distance and the direct current short distance systems may both remain, but it seems doubtful whether the mixed system with rotary converters finds permanent place.

Naphtha launches under ordinary circumstances are perfectly safe, but with any form of liquid fuel a certain amount of care must be exercised. An explosion recently occurred at Great Neck, L. I., which was caused by lighting a match near the naphtha tank. Immediately there was a tremendous explosion. The burning naphtha was scattered in every direction, setting fire to the launch and to the clothing of the owner and his wife, who immediately jumped into the water.

## Hardness of Metals.

F. Auerbach's definition of hardness is given for the case of plastic bodies, including metals, by the limiting pressure per unit surface, attainable between a lens and a plate of the same substance, says Science Abstracts. In the case of metals the deformation cannot be observed with the same facility as in the case of transparent bodies, but the surface of contact may be measured by covering the lens with a thin layer of lampblack. This is only necessary at small pressures, since at great pressures the deformed area retains its shape. A complication is introduced by the fact that the hardness is considerably influenced by small impurities, as well as by the elastic and thermal history of the metal. The author gives the following table of the hardness of various fairly well-defined metals, as compared with minerals:

Steel.....	361	Quartz.
Copper (hard).....	145	Apatite.
Brass.....	137	Fluorapatite.
Brass.....	107	Fluorapatite.
Gold.....	97	
Copper.....	85	Calcifer.
Silver.....	81	
Aluminum.....	83	Boracic Acid.
Lead.....	10	Gypsum.

The aluminum was alloyed with 6 per cent copper. The bronze was an alloy of 15 parts copper, 2 parts zinc, and 1.5 tin. The brass contained 2 parts copper to 1 of zinc.

## Shipping at Nagasaki.

Consul Harris, of Nagasaki, February 9, 1901, reports the launching, on the 26th ultimo, of the steamship "Kaga Maru" from the Mitsu Bishi Dock Yard and Engine Works, of that city. This vessel was constructed under the shipbuilding encouragement act of the Japanese Government and Lloyd's rules, class 100, A1, and was built to the order of the Nippon Yusen Kaisha (Japan Mail Steamship Company) for its American line. The materials used in its construction were purchased in England, and the keel was laid on the 20th of March, 1900. The ship is to be completed and delivered in March, 1902. A description follows: Type, 3 decks; material, steel; length over all, 459 feet; beam, 49 feet 2 inches; depth, 33 feet 6 inches; gross tonnage, 6,240 tons; displacement, 11,800 tons; draft, 25 feet; dead-weight capacity, 6,820 tons; engines, twin-screw, triple-expansion; boilers, cylindrical, four in number; indicated horse power (estimated), 4,500; speed, 15 knots.

## THREE RECENTLY PATENTED NOVELTIES.

Three interesting inventions which have been patented in the United States within the last few months are an adjustable gun-stock, a combined rocking-chair and cradle, and a single-wheel vehicle.



AN ADJUSTABLE GUN-STOCK.

The gun-stock is the invention of Mr. Joseph N. Zoeller, a resident of St. Matthews, Ky. Within the stock an adjusting-head is pivoted and attached to the grip. The head is provided with peripheral teeth, between the spaces of which a bolt, held in the stock, may enter. A manipulating device is provided for the bolt, which device is passed to the outside of the stock for convenient operation. To change the inclination of the stock, the bolt is carried out of engagement with the adjusting-head. After the grip has been moved the bolt is allowed to enter the most convenient space between the teeth to hold the stock and grip as adjusted.

Samuel S. Arnold, of Toronto, Canada, is the inventor of the combined rocking-chair and cradle. The upper and lower bars connecting the rockers of the chair are grooved to receive the corresponding bars of a cradle provided with a rocker at one end. Plus limit the movement of the cradle. When not in use the cradle can be pushed under the chair.

Perhaps the most curious invention is Mitchell R. Heatherly's single-wheel vehicle. Our illustration shows the construction so plainly that an extended description is hardly necessary. Broadly, the contrivance consists of a curved tongue pivoted to the harness, and a single wheel carried by the lower end of the tongue. Above the axle of the wheel are stirrups for the rider or driver, if we prefer to call

him so. Suitable handles are provided on the tongue, which are to be grasped for security. The tongue, it should be observed, is so connected with the harness that it will adapt itself to the motion of the horse. Mr. Heatherly lives in Mundell, Kans. His vehicle is designed to take the place of the bicycle and to be used on race courses.

## The Development of Wireless Telegraphy in England—Its Proposed Adoption in the Post Office.

Some months ago, when the utility and widespread advantages of Marconi's invention were conclusively established, a Departmental Commission of the English Post Office was formed to consider the merits of the system and the advisability of its adoption throughout the British postal service. The report of this



COMBINED ROCKING-CHAIR AND CRADLE.

commission is now complete, and it is stated to relate favorably upon the scheme in its general principle.

The result of this commission consequently portends a great revolution of the English telegraphic service. For several months past the telegraph authorities have been endeavoring to satisfactorily cope with the exigencies of the rapidly increasing telegraph traffic, but the country is so comparatively small, and the congestion of the traffic so acute, that practically no headway has been made toward the solution of the difficulty. If Marconi's system were employed the possibility of blocks on the lines would be entirely obviated, since each telegraph office would have its own synchronized receiver, and only the transmitter corresponding with that receiver would be able to establish communication therewith. Then, again, in stormy weather widespread damage is caused to the wires, frequently destroying communication, while in connection with Marconi's system it has been proved to work better in boisterous weather. These salient characteristics have impressed the commission, and have no doubt appreciably influenced their favorable decision.

Yet the scheme will have to be well prepared, since its innovation is attended with numerous difficulties, some of which can only be obviated by Parliamentary measures. For instance, the British Post Office has a monopoly in any system of telegraphy, and it is only natural to expect that they will endeavor to enforce these rights in the present case. In this event Marconi will be prevented from establishing independent installations without the official license. It is generally believed that at the present time the Post Office does actually claim the monopoly of wireless telegraphy in the British Isles, and that Marconi has not yet received the necessary license to install his system. This belief is somewhat supported by the fact that the English government will not permit wireless telegraph communications to be transmitted from a point less than three miles from the shore. This fact was established at the inauguration of the system upon the mail packet service between Dover and Ostend, when the authorities would not permit the establishment of a land station at Dover. The Post Office is awarded this monopoly by act of Parliament, and it is practically certain that if necessary they will enforce that prerogative. But such a contingency is hardly likely to arise. Marconi has placed himself at the disposal of the commission and has extended them every assistance in his power, in order that the advantages of the system might be thoroughly understood. That the system will be nationalized there is not, the slightest doubt, as in the cases of the tele-


phone and the District Messenger Agency of London.

For once England is desirous of leading the way. Negotiations have already been opened with one or two of the European powers, concerning the idea of establishing the system partially, if not entirely, upon the Continent. By this means the cables will be dispensed with, and the international messages transmitted through the air. Of course there is the question of expense, because such a radical revolution could not be effected except with a great outlay. Yet the system is cheap to install, for the cost is limited to the purchase of transmitters and receivers. Wires, poles, and cables are entirely dispensed with. It will even be unnecessary to erect the lofty pole in connection with the apparatus, since Marconi has invented a cylindrical appliance which performs the same functions with equal satisfaction, as described in a recent issue of the SCIENTIFIC AMERICAN.

Another instance of England's desire to encourage the utilization of the system is proved by the decision of the Admiralty to equip all the vessels in the fleet with the apparatus. Several ships are already supplied, but those which are yet deficient in this respect are being fitted with all possible speed. In a few weeks' time the report of the commission will probably be published, together with the suggestions for acquiring the system from Marconi without interfering with the legality of his patents. Certainly the action of the British authorities will be followed with keen interest by the other nations, and should Great Britain decide upon its immediate introduction other nations will be compelled to do likewise.

## Demand for Blood-Oranges in Germany.

Consul Hughes writes from Coburg, April 26, 1901, as follows: There is a great demand in Germany for the so-called "Italian blood-orange." The popular idea here is that this fruit is colored, not by nature, but by injections of some artificial vegetable dye. To discover the truth or fallacy of this belief, several well-known German chemists have been experimenting, first, to find out from the blood-orange itself if its color is due to artificial means, and, secondly, to change the common Italian orange into a blood-orange by injections of different kinds of coloring matter. The experiments, however, have not been attended with success. It was found that no single injection of any solution would color more than one part of the orange, and that if several injections were made, the fruit was likely to decompose very quickly. The theory was then advanced that the coloring was produced by watering the roots of the trees with a blood-red veget-



A CURIOUS VEHICLE.

able solution. It is needless to say this experiment was as barren of results as the first.

## The Current Supplement.

The current SUPPLEMENT No. 1330 has many articles of general interest. The Racing Yacht "Independence" is accompanied by two illustrations, showing the bow and the remarkable rudder. "Protection of Ferric Structures," by M. P. Wood, is a continuation of a most important paper. "Resistance to Death Among Insects" is a most curious natural history article. "Recently Discovered Greek Masterpieces" is accompanied by a number of engravings made from photographs showing the remarkable nature of the find. "Packing Goods for Foreign Markets," which was commenced in SUPPLEMENT No. 1329, is concluded in this issue and shows how goods of all kinds should be packed for export.

## Contents.

(Illustrated articles are marked with an asterisk.)	
Automobile news.....	407
Automobile race, speed in.....	407
Rigging in the world.....	407
Books, new.....	411
Butter-rolling.....	404
Cars, utilizing railroad.....	410
Chair and cradle, rocking.....	405
Chicago, water supply of.....	405
Clark, T. C.....	405
Comet, electric line.....	407
Cruisers, reconstruction of German.....	407
Docking accident.....	404
Ferryboat disaster.....	407
Gun stock.....	410
Heavens in July.....	403
Light, arc, Nernst.....	407
Mail-box, house.....	404
Metals, hardness of.....	410
Mineral resources.....	408
Nagasaki, shipping at.....	410
Paper, fire from waste.....	403
Photographic printing.....	404
Photography, quick.....	407
Providing a transatlantic line.....	401-403
Snail, self-cleaning.....	404
Steamships, coastwise.....	402
Street car, motors for.....	410
Vehicle, curious.....	410
Wireless telegraphy in England.....	410



## RECENTLY PATENTED INVENTIONS.

## Electrical Apparatus.

**SWITCH FOR ELECTRIC LAMPS.**—CHARLES WAGNER, Manhattan, New York city. The switch is arranged to permit one conveniently to turn the current on or off. The appearance of the lamp is improved, especially when the device is applied to the candle-type of lamp. The unsightly key heretofore used in electrical switches is dispensed with, and a sleeve employed for opening and closing the switch.

**ELECTRIC-CLOCK SIGNAL.**—HARRY B. VAUGHAN, Little Rock, Ark. The signal-clock is of that form in which the clock-hands are made to touch contact-points on the face of the dial, and, by closing an electric circuit at any particular point or hour or number of points, to ring at that hour any particular bell or number of bells. The present invention consists in the peculiar arrangement of such devices whereby any number of guests in a hotel can be automatically called at any particular hour, and whereby all the guests of the hotel are alarmed in case of fire. An alarm-signal can be sounded in any one of the rooms, and an electric lamp lighted by one automatic mechanism.

## Mechanical Devices.

**PUNCHING-MACHINE.**—GEORGE M. ROGERS, Manhattan, New York city. The machine is designed to indicate upon a dial the force of a blow struck upon a pad. The blow has no direct influence on the indicator-hand, but merely deflects an intermediate lever to a greater or less degree, according to the force of the blow, to which position it is held by a locking device. The lever acts as a stop-device to determine the drop of a rod which operates the indicator-hand.

**SAFETY-CATCH FOR ELEVATORS.**—HENRY JEWELL, Butte Mont. The safety-catch is to be applied to the lower deck of a car and to be operated from the king-bolt to which the hoisting-cable is applied. While the hoisting-cable is in good condition and supports the car, the catches are inactive. But as soon as the cable breaks, the catches are automatically forced beyond opposite sides of the car into engagement with the wall of the shaft, or with racks or their like.

**LOCK.**—IRA W. ABBOTT, Nevada City, Cal. The novel feature of this padlock is a slide unlocked and moved by a key and adapted to engage a spring-pressed knee-joint bolt. This bolt is pivoted and designed to engage with its free end the shackle of the bolt. The lock cannot be picked unless the person has the proper key. The lock is simple and durable and can be cheaply manufactured.

**HYDRAULIC AIR-COMPRESSOR.**—LEE E. MITCHELL, Boston, Mass. Mr. Mitchell has improved the air-compressor which he invented in 1900. In the power-cylinder a piston reciprocates. Valve-chests open into the cylinder at the ends and have waste-outlets. A supply connection is provided between the valve-chests. A reciprocating-valve is arranged alternately to open and close the connection to the valve-chests and alternately to close and open the discharge for the waste-outlets from the valve-chests. The piston-valve is actuated by a shaft mounted to rock and provided with a lug. On the shaft a crank-arm is mounted loosely and connected with the valve-stem of the piston-valve, the crank-arm having spaced shoulders adapted to be engaged alternately by the lug on the shaft. The shaft is rocked from the piston-rod of the power-cylinder.

## Railway Appliances.

**PNEUMATIC PACKAGE-HANDLER.**—GEORGE H. WALL, Cadillac, Mich. This package-handler consists of an air-cylinder located at each side of the car-doorway, the pistons being attached to a section of the car-door. The arrangement provides a platform about five feet long and having a width equal to that of the car-door. A governor maintains the level of the platform during operation. Air is drawn from the train-line into a special reservoir for the operation of the device. A forty-day test was given to the first machine to show that air from the train-line could be used for the purpose of loading and unloading baggage. The inventor is an old and experienced railroad man.

**CAR-COUPLER.**—MARK A. BROWN, Douglas, Ga. The coupling belongs to that class in which the drawhead is provided with a pivoted member or knuckle adapted to be locked after engagement with a similar knuckle on another car. In the present invention provision is made to allow a yielding lateral movement of the locking-pin.

## Miscellaneous Inventions.

**DRAPERY-HANGER.**—JOSEPH LANGLOIS, Leominster, Mass. The invention is a drapery-hanger designed to be erected in houses to form an enclosure for coffins. The essential feature is a brace or truss for the side-bars of the drapery-hanger, the brace having a crotch or fork between its ends and a hook at each end. The crotch engages the side-bar and its ends with the hooks, which are adapted to pass around the bar.

**WICK-TRIMMER.**—ROBERT M. JOHNSON, Lancaster, Penn. This simple device serves to clamp a wick to be trimmed. By its means, the wick is compressed at its exposed or igniting surface; moreover, a straight hori-

zontal line is established at the charred portion and a substantial surface is obtained at each side. Upon these surfaces the shears or scissors may bear, and over the surfaces the wiping material may be drawn.

**RETURN-FLOW SYRINGE.**—DENWOOD N. L. NEWSBURY, Manhattan, New York city. The syringe consists of a tube having apertures in its sides, and a shield within which the tube is contained. This shield comprises a body section having a series of curved bars, and a front section in the form of a loop with which the outer ends of the bars are joined. The inner ends of the bars are connected with a perforated cap-plate. The outer end of the tube extends out through the loop-section; and the inner end of the tube screws into a collar connected with the apertured cap-plate. A receptacle is carried by the lower portion of the loop-section.

**HAT-BOX.**—BENJAMIN F. PORTER, Manhattan, New York city. The hat-box is so constructed that the hat can be raised at the bottom of the box, lifted to the top, and held in its raised position without injury. Thus the hat can be brought into position for inspection or for careful removal.

**PIANOFORTE.**—HERBERT S. PERCY A., and OWEN E. READING, 18 Albion Road, Tunbridge Wells, England. The invention relates to improvements in pianofortes in which a sound-board formed of a rolled or cast-plate or sheet of aluminum or aluminum alloy is employed. In order that the instrument may withstand the effects of a hot, damp climate so prejudicial to the ordinary wooden sound-board. Moreover, the resonance is increased; a longer sustaining power is obtained; and the quality of the tone is improved.

**JEWEL-HOLDER AND FASTENING DEVICE FOR CORD COLLARS.**—SHERWOOD B. ROBERTSON, Brooklyn, New York city. The device is intended to be used with cord collars worn by Masonic fraternities. The invention provides a neat and efficient means of holding the ends of a collar, at the same time allowing the ready attachment of ornaments or jewels and presenting an outer surface suitable for the production of emblems or other ornaments.

**SAW-GAGE.**—DANIEL C. STEELE, Village Mills, Texas. Mr. Steele has devised an improved saw-gage more especially designed for use on saws having cleaner-teeth and arranged to permit accurate filing of the cleaner-teeth without leaving an undesirable burr and without danger of filing the teeth too short for proper working in a cut.

**WELL-DRILLING APPARATUS.**—MILTON LATTA, Burwell, Neb. The apparatus is light and readily portable. It can be operated by hand, thus avoiding the necessity of horsepower. The pump-valve is not subjected to the action of the mud, dirt and gravel drawn up through the well-tube. The revolving chamber is closed by a construction which can be readily removed for the purpose of cleaning it out. The current through the drill is fast and strong enough to draw up gravel. All work is performed on the ground surface. The strain or suction is always inward, so that in case of breakage or a leak at any point the mud, water, and the like will not be thrown outward upon the operator.

**NOTE.**—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.

## NEW BOOKS, ETC.

**NEW LANDS. Their Resources and Prospective Advantages.** By Hugh Robertson Mill. London: Charles Griffin & Company, Limited. Philadelphia: J. B. Lippincott Company. 1900. With ten maps. Pp. 280.

The present volume deals with a subject which is of great interest, in view of the present tendency for persons to leave the old countries and emigrate to new lands. The book presents, in a simple and practical manner, the conditions of life in those parts of the world where there is still an opening for the energies of the English-speaking people desiring to make their home or invest their capital in a new country. Little more than the countries of the temperate zone are considered. The author has done his work thoroughly, and it is a book which cannot but prove of value to the audience to which it is addressed.

**WATER POWER. An Outline of the Development and Application of the Energy of Flowing Water.** By Joseph P. Frizell. First edition, first thousand. New York: John Wiley & Sons. London: Chapman & Hall, Limited. 1901. Pp. 563. Price, \$5.

Water power is becoming more and more prominent every day. Recent remarkable developments in electricity and other modes of transmitting mechanical energy have recalled water power to something like its former position in the industrial economy of the world. The changed conditions have given a new interest to this source of power, and directed the attention of investors to sources which formerly appeared entirely outside the range of practical consideration. They have also led to some noteworthy improvements in the utilization, development and transmission of power. The author has done a real service

to civil and hydraulic engineering by writing an admirable book outlining the latest practice. The book has many illustrations, and is well printed and bound.

**THE PRINCIPLES, CONSTRUCTION, AND APPLICATION OF PUMPING MACHINERY.** By Henry Davey. London: Charles Griffin & Company, Limited. Philadelphia: J. B. Lippincott Company. 1900. With frontispiece, five plates and over 250 illustrations. Pp. 295. Price, \$6.

The purpose of this book is to present the information in such a form as will make it most useful to the practical engineer engaged in the application of pumping machinery in mines or elsewhere, or in circumstances under which large quantities of water have to be dealt with. A large number of illustrations are given, showing the typical installations, and there are several full page and folding plates. The practice appears to be largely English practice, but it is certainly of very late types. It is a book which will be indispensable to the hydraulic engineer.

**SUR LES NERFS CEPHALIQUES, LES CORPORA ALLATA ET LE TENTORIUM DE LA FOURMI.** Par Charles Janet.

**ESSAI SUR LA CONSTITUTION MORPHOLOGIQUE DE LA TÊTE DE L'INSECTE.** Par Charles Janet. Paris: Georges Carré et G. Naud. 1899. Pp. 74.

**L'ESTHÉTIQUE DANS LES SCIENCES DE LA NATURE.** Par Charles Janet. Extrait du Bulletin de la Société Zoologique de France Reconnue d'Utilité Publique, Année 1900. Paris: Au Siège de la Société Zoologique de France. 1900. Pp. 8.

**ENGINEERING CHEMISTRY. A Manual of Quantitative Chemical Analysis for the Use of Students, Chemists, and Engineers.** Second Edition. By Thomas B. Stillman, M.Sc., Ph.D. Easton, Pa.: The Chemical Publishing Company. 1900. Pp. 503. With 132 illustrations.

This book was written especially as a manual of quantitative chemical analysis for the use of students, chemists, and engineers. It treats especially of the determination of impurities in the various metals, water for all uses, and various other commercial substances such as paper, lubricating and illuminating oils, paint, cement, and the like. There are also chapters on liquid fuel, petroleum, and asphalt. A classification of the different grades of steel and their uses forms one of the most valuable chapters of the book. There is also an interesting chapter on pyrometry. The book concludes with chapters on the electrical units and energy equivalents, which are especially useful for ready reference. Numerous tables of pressures, temperatures, percentages, etc., are also appended.

**NEW IDEAS. Quarterly Publication of the Romanes Society.** Published by Witherby & Company, Office of Knowledge, 326 High Holborn, London.

We have received the January and March numbers of this pamphlet, which contain Essays Toward a Mechanical Theory of Vital Processes. The Romanes Society was founded at Christchurch, Oxford, in 1897, for the purpose of stimulating and promulgating original thought and research in science; and in New Ideas are printed original articles of merit on scientific subjects.

**THE CHEMICAL ANALYSIS OF IRON.** By Andrew A. Blair. Philadelphia and London: J. B. Lippincott Company. 1901. 320 pp., 105 figures. Price \$4.

This work is intended as a guide for the student of iron chemistry. In it are described many special apparatuses for the performance of analytical work which otherwise only the possessor of a complete chemical library would have at his command. The book has just entered its fourth edition, and has been entirely rewritten and brought up to date. Besides apparatuses for analyzing iron and steel, the author treats of the analysis of slag, sand, coal, coke, and furnace and producer gases also. The book will be found of great value to chemists engaged in this special line of work.

**WATERWORKS DISTRIBUTION.** By J. A. McPherson, A.M., C.E. New York: The D. Van Nostrand Company. 1901. 154 pp., 19 full-page diagrams and 103 other illustrations. Price \$2.50.

This book is intended as a short, practical guide to the laying out of systems of distributing mains for the supply of water to towns and cities. It is by a practical engineer who has had twenty-four years' experience; and contains much valuable data, together with numerous illustrations of the various valves and other apparatus employed in an up-to-date supply system. A large chart of an example district, showing distribution, is added to the other diagrams.

We acknowledge the receipt from the Director of the Sydney Observatory of New South Wales, Australia, of a report on the Results of Meteorological Operations in New South Wales during 1898, which is used in the Department of Public Instruction on Meteorology of New South Wales. It is very complete in its arrangement of items of special interest.

## Business and Personal Wants.

**READ THIS COLUMN CAREFULLY.**—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. In every case it is necessary to give the number of the inquiry.

MUNN &amp; CO.

Marine Iron Works. Chicago. Catalogue free.

**Inquiry No. 904.**—For manufacturers of spring motor fans.

**TURBINES.**—Lefell & Co. Springfield, Ohio, U. S. A.

**Inquiry No. 905.**—For parties to manufacture a money bag of canvas and brass.

"U. S." Metal Polish. Indianapolis. Samples free.

**Inquiry No. 906.**—For the manufacturers of the James Cash Lock.

**WATER WHEELS.**—Alcott & Co., Mt. Holly, N. J.

**Inquiry No. 907.**—For parties to manufacture of water wheels or any form of hydraulic power.

Yankee Notions. Waterbury Button Co., Waterbury, Ct.

**Inquiry No. 908.**—For parties engaged in cutting out sheet metal letters in tin or brass.

For bridge erecting engines. J. S. Mundy, Newark, N. J.

**Inquiry No. 909.**—For manufacturers of small spur gear wheels and sprocket wheels.

Machine chain of all kinds. A. H. Bliss & Co. North Attleboro, Mass.

**Inquiry No. 910.**—For the address of the toy and games "Paradise" and "Wooden."

Handle & Spoke Mch. Ober Mfg. Co., 10 Bell St., Chargin Falls, O.

**Inquiry No. 911.**—For parties to manufacture an article composed of small glass tubing and of special dimensions.

Sheet Metal Stamping; difficult forms a specialty. The Crosby Company, Buffalo, N. Y.

**Inquiry No. 912.**—For manufacturers of miner's novelties, also for the address of a newsdealer to supply quantities of newspapers, magazines, etc.

Sawmill machinery and outfit manufactured by the Lane Mfg. Co., Box 15, Montpelier, Vt.

**Inquiry No. 913.**—For manufacturers of blowers or injectors, fuel oil injectors, air and oil injectors, operated by steam or compressed air.

For Sheet Brass Stamping and Small Castings, write Badger Brass Mfg. Co., Kenosha, Wis.

**Inquiry No. 914.**—For manufacturers of drill presses, electrical tools, boilers, engines, dynamos, motors, laundry machinery, etc.

Rigs that Run. Hydrocarbon system. Write St. Louis Motor Carriage Co., St. Louis, Mo.

**Inquiry No. 915.**—For manufacturers of automatic piano-playing devices.

Ten days' trial given on Daus' Tip Top Duplicator. Felix Daus Duplicator Co., 5 Hanover St., N. Y. city.

**Inquiry No. 916.**—For manufacturers of wheels for wheel barrows.

SAWMILLS.—With variable friction feed. Send for Catalogue B. Geo. S. Conestock, Mechanicsburg, Pa.

**Inquiry No. 917.**—For parties to furnish oval rosewood handles by the gross, for harness makers' round knives.

Wanted.—Punch and Die Work, Press Work and Light Manufacturing. Daugherty Novelty Works, Kittanning, Pa.

**Inquiry No. 918.**—For manufacturers of small gasoline motor castings of 1/4 or 1/2 horse power.

Manufacturers of Valves, Fittings, Brass and Iron Work. Spindler & Deringer, 12-22 Morris St., Jersey City, N. J.

**Inquiry No. 919.**—For manufacturers of castings for small model steam engines, also of supplies for small boilers.

Inventions developed and perfected. Designing and machine work. Garvin Machine Co., 149 Varick, cor. Spring St., N. Y.

**Inquiry No. 920.**—For manufacturers of screw wrenches, etc.

The celebrated "Hornsey-Akroyd" Patent Safety Engine is built by the De La Vergne Refrigerating Machine Company. Foot of East 128th Street, New York.

**Inquiry No. 921.**—For manufacturers of pine poles and barrels for salt fish.

The best book for electricians and beginners in electricity is "Experimental Science," by Geo. M. Hopkins. By mail, \$4. Munn & Co., publishers, 361 Broadway, N. Y.

**Inquiry No. 922.**—For manufacturers of automobiles (gasoline system) to carry 2 persons up a grade of 15 per cent over country roads. A twin cylinder machine preferred.

Will give a one-half interest in twelve inventions, or any part of number, for money to perfect patent and dispose of same. Address S. O. Stewart, El Las Vegas, New Mexico.

**Inquiry No. 923.**—For a half mile of second-hand rails to hold cars loaded with five tons of lumber.

**ELECTRICAL ENGINEER (Tramways).**—Wanted immediately by the Council of the City of Wellington, New Zealand, a thoroughly qualified Electrical Engineer, who must have had special experience in carrying out and equipping overhead electrical tramways and power stations. Full particulars and conditions may be obtained on application to Messrs. B. W. Forbes & Son, Produce Exchange, New York, and applications must be delivered at the office of Messrs. John Duthie & Co., Ltd., Lime Street, London, E. C., England, not later than noon on the 28th July.

**Inquiry No. 924.**—For manufacturers of lightning rods.

IMPRESSED UPON HIS NOTICE.

The various features for which the Lackawanna Railroad has become noted are involuntarily impressed upon the notice of the passengers, who realize the luxury of hotel or club appointment in the electric lights; the smooth-running journals of the wheels; the extraordinary cleanliness made possible by the use of anthracite coal, avoiding all dust and nauseating smoke; the consciousness of being always on time—which comports for an ease of mind and body most favorable to the enjoyment of the unsurpassed scenery through which its lines pass. It is but the natural sequence that the Lackawanna is prosperous in like degree to its excellence of service and its warm friends are equal in number to its whole list of patrons, for once to test its service means an ardent admirer and friend earned for the road.—Van Etten Bros.

**Inquiry No. 925.**—For parties to manufacture several thousand aluminum models of a special character.

We do Experimental Special and Automatic Machine, Tool, Die and Model Work, also Metal Stamping. Racine Model Works, Racine, Wis.

**Inquiry No. 926.**—For manufacturers of stereo-










**ENGINE & FOOT LATHES.** MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. EST. 1882  
SEBASTIAN LATHES CO. CINCINNATI, O.

# HOT BLAST

## WATER JACKET FURNACES FOR COPPER ORES.

## A Tool Inventory



**Montgomery & Co.'s  
Tool Catalogue**

a book of 510 pages, illustrated, well  
printed, pocket size, and mailed to any  
address on receipt of 25 cents.

**MONTGOMERY & CO.,**  
105 Fulton St., N. Y. City

The maximum of strength, durability and safety, with the minimum of cost that description can give, is the **Hoisting Engines** for operation on Gasoline, Distillate or Crude Oil. Every part of the engine is interchangeable. Some save its cost in fuel alone. Each friction and geared hoist, 5 to 150 h. p. For cranes, rollers, and derrick. **Wherry & Sons, Gasoline Engine Co.**, P. O. Box 1114-6, Kansas City, Mo.



**KEROSENE  
and Gas Engine**

burns **KEROSENE**  
cheaper and safer than gaso-  
line. Automatic, simple, re-  
liable. No electric battery  
or flame used. Perfect regu-  
lation. Belted or directly  
coupled to dynamo for elec-  
tric lighting, charging storage  
batteries, pumping and  
all power purposes.

**Th. "Wolverine" Three Cylinder Gasoline Marine Engine.**

The only reversing and self-starting gasoline engine on the market. Lightest engine for the power built. Practically no vibrations. Absolutely safe. Single, double and triple marine and stationary models from 2 to 20 H. P.

**WOLVERINE  
MOTOR WORKS.**

Written for catalog



**PALMER BROS.,** - - **MIANUS, CONN.**

attained in the

**STOVER  
GASOLINE  
ENGINE**

The best is always cheap-  
est. Write for prices.

**STOVER ENGINE WORKS, FREEDPORT, N.Y.**



# TELEPHONES

## SOLD OUTRIGHT.

All kinds of Telephone Apparatus. Absolutely guaranteed. Switchboards for large or small exchange.

**HOLD ON THERE!**

Send us for catalog of  
**Monarch Marine  
Gasoline Engines**  
34 to 45 H. P. \$30 up.

**Grand Rapids Gas  
Engine & Yacht Co.,  
Grand Rapids, Mich.**

Lubricator, J. Baumhoer.....	670,672
Magnetic separating apparatus, T. A. Ed- mondson.....	670,840,
Mail box, C. O. Giers.....	670,841
Mail pouches to railway catchers or cranes, attachment for fastening, L. L. Henry.....	670,842
Masonry, cast, and dry-not proof air- C. Lorinc.....	670,843
Massage instrument, L. S. Fritze.....	670,907
Match box, C. P. Mullins.....	670,904
Match box, C. P. Mullins.....	670,908
Mechanical device for separating and Mearns.....	670,910
Mechanism, liquid, A. Hase.....	670,950
Mechanical movement, E. Gundlach.....	670,937
Metal feeding and melting mechanism, Gro- ar.....	670,990
Miner's lamp, N. K. Bowman.....	670,930
Mineral squib, I. T. Jenkins.....	670,902
Mold, See Concrete construction mold.....	670,924
Mortar, D. B. Hill.....	670,925
Mot wrighting, H. A. Hayden.....	670,937
Music leaf turner, F. S. Duell.....	670,945
Myroscope, automatic, A. Peterson.....	670,946
Nail puller, W. M. Carron.....	670,940
Nut lock, W. O. McCarron.....	670,940
Nut lock, W. S. Ellifritz.....	670,978
Oil can, W. M. Owen.....	670,977
Ordnance, J. W. Kline.....	670,940
Ore concentrator, T. Dynan.....	670,940
Ore roasting apparatus, H. Carmichael.....	670,940
Ores, separating metallic from rocky con- stituents of, F. E. Elmore.....	670,940
Ornamental fabric, J. Macadam.....	670,944
Overall suit, union, McDaniel & Singrey.....	670,947
Oxidizing apparatus, A. N. Dubois.....	670,947
Package for semi-solids, non-refillable, L. G. Price.....	670,944
Paint cans, composition for lining, G. A. Will.....	670,950
Pan, S. L. Depew.....	670,924
Paper box, W. M. Kollmer.....	670,920
Paper box, W. B. Grim.....	670,947
Paper cutter, W. F. Hutchinson.....	670,963
Pen, drawing, J. M. Barnay.....	670,942
Perforating machine, H. Hollerith.....	670,943
Pile rack, A. O. Bobem.....	670,932
Piles, protecting woodwork, S. L. Shumston.....	670,900
Pipe coupling, O. Ledovsky.....	670,944
Pipe joint former, W. H. Hermer.....	670,948
Pipe joint, swivel, T. W. Fulton.....	670,948
Piston, J. G. Kitchen.....	670,948
Pitman, J. K. Johnston.....	670,950
Plastic material, cutting table for, A. Snell. Hopper.....	670,940
Printing plate and impression surface hold- er, F. G. Price.....	670,913
Printing press, W. H. R. Toye.....	670,913
Printing press, W. H. R. Toye.....	670,913
Printing presses, making ready forms for, F. G. Price.....	670,912
Printing press, cylinder, Knapp & Vogel.....	670,917
Pulley, self-selling, A. A. Brown.....	670,910
Pulp, apparatus for the manufacture of long-stapled wood, J. O. Klimesch.....	670,940
Pump, Spence & Laflerty.....	670,978
Pumping and reciprocating mechanism, S. W. Luttrell.....	670,942
Punching mechanism, cabinet, B. Stinson.....	670,980
Rack, M. Shaughnessy.....	670,980
Rolls for re-rolling, machine for preparing, J. F. Craven.....	670,980
Rails, renewing steel, D. H. Leutz.....	670,980
Railway bumper, A. C. McCord.....	670,930
Railway of like vehicles, electrohydraulic coupling, W. S. Miller.....	670,943
Railway, single track, A. A. Welsh.....	670,970
Rake, G. J. Adam.....	670,920
Receptacle or envelop, C. A. Hall.....	670,943
Refrigerator, S. Northey.....	670,960
Refrigerator, G. L. Wyman.....	670,960
Regulator, C. H. Seeler.....	670,920
Revolver, Smith & Wesson.....	670,920
Revolving machine, A. C. Williams.....	670,927
Rolling mill feed tables, billet turning de- vice for, J. F. Craven.....	670,920
Rose engine, F. Schirmer.....	670,911
Rotary engine, A. S. Platt.....	670,987
Rotary engine, A. Stewart.....	670,978
Saddle harness, S. A. Marker.....	670,927
Saggers, making, A. Weber, Jr.....	670,960
Saw balance, D. Hoyt.....	670,980
Sawmill saw guide, band, W. A. Wilkinson.....	670,982
Sawmill saw straining device, band, W. A. Wilkinson.....	670,980
Scale, platform, H. Farin.....	670,940
Scale, weight weighing, G. H. Conant.....	670,901
Scale removing and valve grinding device, E. W. Crowley.....	670,917
Scraping, C. W. Wray.....	670,980
Scraper, T. J. Henry.....	670,932
Separating and separating apparatus, P. A. Arnold.....	670,945
Seat, F. B. Hunter.....	670,915
Seat, F. W. Hunter.....	670,908
Secretary for travelers, portable, F. W. Hall.....	670,930
Sectional heater, E. Porter.....	670,940
Shedding machine, E. O. Cowles.....	670,974
Sewing machine embroidery attachment, F. O. Moore.....	670,978
Sewing machine keeper mechanism, L. G. Shade, adjustable, window, A. H. Hover.....	670,980
Shade fixture, window, J. Hoyt.....	670,943
Shade holder, window, J. Hoyt.....	670,943
Shaft support, C. McE.....	670,973
Sheet metal, metal foil, etc., apparatus for the manufacture of, Heinrich & Bosch.....	670,919
Shell potting, hanging, L. Faetho.....	670,919
Shell feeding device, L. L. Morris.....	670,901
Shifting device and brake, combined, O. B. Hitt.....	670,987
Shoe, last fastener, C. W. Lord.....	670,933
Shoe walnuts, skirts, and bolts, supporter for, F. G. Dietz.....	670,970
Shoe tree, C. McGovern.....	670,970
Sifter, ash, C. McGovern.....	670,925
Signal actuating apparatus, H. P. Maxim.....	670,984
Signal lifter, L. A. Yost.....	670,944
Smelting process of fusing sodium com- pound electric, A. R. Cowles.....	670,977
Smoke consuming furnace, Reed & Sonick.....	670,980
Soldering iron, self-heating, F. E. Benier.....	670,907
Spindle appliance for predetermining, D. H. Hitt.....	670,943
Spinning apparatus, yarn, Willey & Mc- Daniel.....	670,920
Spinning apparatus, yarn, G. O. Draper.....	670,920
Spittoon, B. Gray.....	670,940
Stacker, hay or grain, A. Bouchey.....	670,942
Stacker, breaded grain, J. Francoeur.....	670,964
Stacker, pneumatic, A. E. Wright.....	670,982
Straw, M. B. Kassel.....	670,984
Stationary packet, J. J. White.....	670,987
Steam boiler, vertical, J. Patterson.....	670,987
Steam cylinder driver, vertical, J. Patterson.....	670,987
Steam engine, I. Sedgewick.....	670,901
Steam in steam power apparatus, utilizing the heat of oil, of the Osterenger.....	670,985
Steel trap, Mosser & Cooke.....	670,940
Stomach pump, of open heart, S. T. & C. H. Wellman.....	670,943
Stop motion, J. J. Eastman.....	

**THE HUB**  
will keep you posted on  
**Automobiles.**  
At news stands or by mail,  
25 cents. Six months'  
subscription \$1.00.  
**THE HUB,**  
Room 6,  
24 Murray St., New York.



## YOUR BICYCLE

## THE NEW BRISTOL COUNTER

Registers an accurate account of work done on printing presses, grain sales, weighing, measuring and other automatic machines. Counts up to 1,000,000 and repeats automatically. Simple, accurate, durable. See also counters in order. Send for circular.

**C. J. ROOT, Bristol, Conn., U. S. A.**

**AUTOMOBILE AND MARINE**  
**MOTORS AND TRANSMISSIONS.**  
FOR THE **BEST** WRITE TO  
**BUFFALO GASOLINE MOTOR CO.**  
10-20 BRADLEY ST. BUFFALO, N.Y.

**The Worcester Polytechnic Institute,**  
WORCESTER, MASS.  
T. C. MENDENHALL, Ph.D., LL.D., Pres't  
Courses of study in Mechanical, Civil and Electrical Engineering, Chemistry and General Science. New and extensive laboratories in Engineering, Electricity, Physics, and General and Industrial Chemistry. Special facilities in Hydraulics. 30-page catalogue, showing appointments, courses, *tuition, graduate studies, free.*  
Address J. B. MARNHALL, Registrar.



**A Reliable and Simple  
FOUR CYLINDER  
Gasoline  
Motor**

**6½ Brake Horse Power Guaranteed for Marine and Automobile use. Free from vibration, variable speed, starts on quarter turn. Prompt delivery. Additional information cheerfully given.**

*Catalogue for the asking.*

**MOTOR VEHICLE POWER CO., 1229 Spring Garden St.  
N.Y. Office, 62 Gold St. Philadelphia.**

**THE JOHNSON ROTARY PUMP.**  
Simple of construction, positive in action, easy and quiet in operation. Especially adapted to pumping soap, oil, sugar, lard, glue, acids, starch, dyes, varnish, corn and water, malt, etc. Large sizes for irrigation.

Made on a belt or steam pump, or combination, or operated by electric motor or gasoline engine. No leakage.



**DAVIS-JOHNSON CO.,** Station V, CHICAGO, ILL.  
25 Liberty St., New York City.

**GERE GASOLINE ENGINES**  
SIMPLEST BOAT ENGINES MADE  
**CABIN AND OPEN BOATS**  
ENGINE CASTING BOAT FRAMES  
610. N. GERE YACHT LAUNCH WKS.  
NEW CAT FOR 4 STAMPS  
GRAND RAPIDS, MICHIGAN

**Queen Transits and Levels**  
High Grade Instruments with the Latest Improvements  
140 page Engineering Catalogue on application.

**THE QUEEN**

240 page Mathematical Catalogue on application.

**ENGINEERS' AND DRAFTSMEN'S SUPPLIES**  
**QUEEN & CO.,** Optical and Scientific Instrument Works,  
59 Fifth Ave., New York. 1010 Chestnut St., Phila.



## ARTESIAN

Wells, Oil and Gas Wells drilled by contract to any depth from 50 to 500 feet. We are manufacturers and furnish everything required to drill and complete same. Portable Horse Power and Mounted Steam Drilling Machines for 10 to 150 feet. Write us stating exactly what is required and send for illustrated catalogue. Address

**PIERCE WELL ENGINEERING CO.**  
150 LIBERTY STREET, NEW YORK, U.S.A.

**GASOLINE MOTOR CASTINGS**  
For MARINE, VEHICLE and  
BICYCLE MOTORS,  
with Working Drawings.  
LOWELL MODEL CO., 22 Wiggins St., Lowell, Mass.

**GEARS, UNION MODELWORKS, CATALOGUE FREE**  
MODEL SUPPLIES 194 S. CLARK ST. CHICAGO

FOR MEN OF BRAINS  
**Cortez CIGARS**  
—MADE AT KEY WEST—

These Cigars are manufactured under the most favorable climatic conditions and from the mildest blends of Havana tobacco. If we had to pay the imported cigar tax our brands would cost double the money. Send for booklet and particulars.

**CORTEZ CIGAR CO., KEY WEST.**

**SMALL STEEL CASTINGS**

That are Moulded True to Pattern.  
That are of Tough and Uniform Metal.  
That are Easily Machined (No hard spots).  
That are Free from Blow or Sand Holes.  
That will take a Fine Polish.  
That will Harden like Tool Steel.


Send Samples for Price Bidding Quantity Required.

**HOMER F. LIVERMORE, 80 Pearl St., Boston, Mass.**

**THE ELECTRIC HEATER.—A VALU**  
able paper, with working drawings of various forms of  
the electrical heaters, including electric soldering iron,  
electric pad for the sick, etc. 6 illustrations. SCIENTIFIC AMERICAN SUPPLEMENT 1112. Price 10 cents.  
For sale by Munn & Co. and all newsmen.



**LOZIER**  
GAS ENGINES  
LAUNCHES




Three handsome and more elaborate catalogues ever published, free on request.

**THE LOZIER  
MOTOR CO.,**  
26 Water Street,  
PLATTSBURG, N. Y.

**The Perfection of Pipe Threading**  
is admitted to be reached when our  
**No. 0% PIPE THREADING  
MACHINE**  
is used. As a hand machine it is the  
only one known that will cut and thread  
an 8 inch pipe with ease and satisfac-  
tion. One valuable feature is, that it  
has no arbitrary lead screw for deter-  
mining style or pitch of thread to be  
cut. For Send for Catalogue

**THE MERRELL MFG. CO.**  
561 Cassius St., Toledo, Ohio.



Price  
\$18.

## GAS ENGINE IGNITERS

for Marine, Stationary and Automobile engines. Will save their cost many times over in one year.

Write for circulars.

The Carlisle & Finch Co.,  
223 E. Clifton Ave., Chelmsford, Mass.


## A PLEASURE LAUNCH

Must have speed, combined with safe and reliable power; she must be built upon lines of grace and beauty. The "Recreation" covers these requirements. In its use you are tranquil in mind, body and estate, no fixing or furling upon "her going." Minimum weight, maximum power, economy of maintenance. Throttle speed regulation. Write for circular.

WESTERN GAS ENGINE CO. MINNEAPOLIS, MINN.

**REVERSING STEAM TURBINE.**—PARSON'S recently perfected turbine for boats. Illustration showing details. Contained in SCIENTIFIC AMERICAN SUPPLEMENT No. 1158. Price 10 cents, by mail, from this office, and from all newsdealers.

**PROSPECTIVE BOAT BUYERS**



By constructing your boat from a set of my **Boat Building Materials** more than one-half the boat factory's price can be realized. Also economize freight and percent. Launches, Sail and Row Boats, Gasoline Engines, *Catalog free.*

**FRED MEDART, 2545 DeKalb St., St. Louis, Mo.**

**Building Edition**  
**Scientific American**

**MONTHLY, \$2.50 PER ANNUM.**  
**SINGLE NUMBERS, 25 CENTS.**

The July Number contains a

Talk with Mr. John M. Carrere on the Pan American Exposition." Another important article is, "The situation of the House," "Colonial Architecture in New York," accompanied by a carefully executed drawing, "English Gardens," has two beautiful illustrations.

**NEW DEPARTMENTS**

Monthly Comment.  
Talks with Architects.  
New Books,  
New Building Patents.  
Notes and Queries.  
Digest of Current Articles  
Household Notes.  
**MUNN & CO.,**  
Publishers, 361 Broadway, New York.



## GOLD MEDAL PARIS

AWARDED AT PARIS


Exposition,  
1900



Handsome Illustrated  
Catalogue mailed on request

## UNDERWOOD

Visible Writing, Universal Keyboard, Speed, Touch.  
**WAGNER TYPEWRITER CO.**  
189 Monroe St., Chicago. 618-000 New York.  
506 Twelfth St., N. W., Washington, D. C.



**NICKEL**  
AND  
Electro-Plating  
Apparatus and Material  
THE  
Hanson & VanWinkle  
Co.,  
Newark, N. J.  
120 Liberty St., N. Y.  
and 208 Canal St.,  
Chicago.

## WAGE CALCULATOR

INSTANTANEOUS. ACCURATE.  
Reckons for Hours, Days and Weeks at rates  
from \$1 to \$25 per week, and 25 to 400 per hour.  
Prevents delay and error.

Needed in Every Establishment Employing Help.  
In book form—100 pages. Sent postage paid on receipt  
of \$1. Address

**KERN & JOB, Pubs., SHAMOKIN, PA.**

A neat little park wagon,  
N. water curbed, fuel tank  
with coil spring device—  
11 wheel to run 250 miles  
without stopping. Weight,  
580 pounds. Five horse power,  
giving one horse power  
to every hundred pounds.  
Price, \$730.



**LOOMIS**  
**AUTOMOBILE COMPANY**  
Westfield, Mass. MODEL NO. 1

## LEROI RACER

Is in every way a strictly up-to-date mount. It is one  
of the handsomest bicycles  
on the market and a pleasure  
to own one. We manufacture  
bicycles in every state of com-  
pletion or complete from \$25  
to \$40 and guaranteed for one  
year. Get our catalogue.



Address Bicycle Dept., John E. Kelm, Buffalo, N. Y.

## TELESCOPE

THE AUTO-CARBURETTOR  
made upon a new principle furnishes a reliable explosive mixture.  
No pump required. Can run on any grade of gasoline with no waste.  
Especially adapted to automobiles and cycle motors. Write us  
for prices and booklet on "Carburetors," "Gasoline and Steam  
Engines and Automobiles" built to order and repaired. **THE**  
**ATV & JENNISON CO.,** 80 So. Canal St., Chicago.



## Telephones,

for Interior, Short Line, Intercom-  
municating and Hotel Work. Write us for  
prices, catalogue, etc., with testimonials  
and references. Estimates cheerfully  
furnished. Agents wanted.

**THE SIMPLEX INTERIOR**  
**TELEPHONE CO.,**  
431 Main St., Cincinnati, Ohio.

## THE Topophone, \$25

PREVENTS MARINE DISASTERS IN  
**FOGS.**  
See Sci. Am., March 20, 1901, or write for Circular to  
J. B. COLT CO., Room 1, 21 Barclay St., New York.

## LYON & HEALY'S BRASS BAND

**Own Make**  
INSTRUMENTS. Endorsed by  
the great Jules Levy as the best in  
the world. Big Catalogue, 60 illus-  
trations, FREE. Positively the  
lowest prices on Band Instruments,  
Uniforms and Supplies of all kinds.  
Also contains Music and Instru-  
ctions for New Bands. Lyon & Healy,  
Manufacturers, 45 Adams St., Chicago.  
Lyon & Healy is the largest mu-  
sic house in the world—Editor.

"The recognized authority on Wiring and Construction."  
**STANDARD WIRING**  
for Electric Light and Power, as adopted  
by the Fire Underwriters of the United  
States, by H. C. CUSHING, JR., A. L. E. E.  
Electrical Engineer and Inspector. In  
use by over 30,000 Electrical Engineers,  
Central Station Managers and Wiremen.  
Because it is the only book on Wiring  
and Construction kept strictly up to date.  
Flexible Leather Cover, pocket size, \$1.  
Sent postpaid upon receipt of price, by  
H. C. CUSHING, JR., 28 Cortlandt Street, New York City.

**Perfection Air Mattresses**  
FOR CAMP YACHT HOME HOSPITAL  
NON-ABSORBENT, HYGIENIC, AIR-RESISTANT.  
When inflated can be rolled into  
small package for storage or transportation.  
Send for Illustrated Catalogue with Prices.  
**Mechanical Fabric Co.** PROVIDENCE, R. I.

Tile mold, building, L. H. de Fernelmont.....	676,020
Tire, elastic wheel, J. H. Langgaard.....	676,562
Tire, inflatable, R. V. Canfield.....	676,733
Tire machine, rubber, R. W. Collier.....	676,948
Tire, solid rubber vehicle, F. A. Seiberling.....	676,570
Tires to channelled vehicle wheels, apparatus for applying taped or wired, J. H. Toole.....	676,452
Tongue, adjustable jaw, J. F. Wilson.....	676,730
Tool holder, G. W. Rogers.....	676,573
Toy, J. D. Dawson.....	676,828
Toy, locomotive, D. P. Clark.....	676,420
Truck holder, car, D. C. Courtney.....	676,421
Typewriter, M. Toblik.....	676,735
Typewriting machine tabulating mechanism, C. Spino.....	676,500
Umbrella support, H. Devine.....	676,501
Upholstery apparatus, J. L. Heffner.....	676,521
Valve, pressure regulating, H. Shoemaker.....	676,794
Valve, steam engine, C. R. Prescott.....	676,855
Vapor absorber, J. Patton.....	676,848
Vaporizer, therapeutic, J. E. Cross.....	676,495
Vegetable topping machine, A. E. Vrooman.....	676,713
Vehicle, P. E. Berger.....	676,549
Vehicle body, H. McLoughlin.....	676,466
Vehicle brake, J. R. Brown.....	676,469
Vehicle coupling and supporting means, C. T. Wygant.....	676,000
Vehicle-mounted crank mechanism, J. C. Moore.....	676,829
Vending apparatus, M. B. Cody.....	676,529
Vessels, apparatus for locating sunken, S. Lake.....	676,531
Vote recorder, A. J. Belling.....	676,820
Wad feeding device, W. L. Morris.....	676,456
Wagon brake, J. W. T. & J. P. Irwin.....	676,750
Wagon wrench, E. Murphy.....	676,559
Wall holder, T. D. Riddle.....	676,611
Wall, partition, slab, block, etc., G. L. Mouche.....	676,980
Wardrobe, F. Vogt.....	676,590
Water cooler and filter, J. P. Meier.....	676,591
Water gages and cocks, device for cleaning the passages of, R. H. Paul.....	676,755
Water motor, W. L. Morgan.....	676,444
Water pump, C. P. Kitzmann.....	676,474
Waterproof method and compound, C. S. Friedman.....	676,485
Wave power, L. A. Broadbent.....	676,493
Weighing appliance, J. Trantier.....	676,905
Wheel track cover, A. J. & E. Secor.....	676,706
Whistle, A. La Rue.....	676,474
Winding machine, A. B. Moore.....	676,751
Window, Browning & Daly.....	676,567
Wire reeling apparatus, W. H. Doran.....	676,529
Wire reeling apparatus, W. H. Doran.....	676,902

### DESIGNS.

Bake pan, W. H. Collins.....	34,698
Bed bottom coupling stud, H. Newbury.....	34,672
Belt, apparel, F. A. Luce.....	34,682
Bicycle frame, H. Jarvis.....	34,673
Bird, J. Schullinger.....	34,685
Blade, D. J. Seaman.....	34,683
Fire kindler, composition, F. C. Rockwell.....	34,677
Game board, J. F. Wegmann.....	34,678
Gas vaporizing frame, C. V. Best.....	34,676
Glass, sheet, C. Hartung.....	34,679
Horseshoe heel pad, J. A. Buck.....	34,674
Knocking board, J. C. Beaumont.....	34,669
Monument or tombstone, E. C. Rodgers.....	34,681
Piston head, C. Perkins.....	34,675
Sewing machine frame, L. Onderdonk.....	34,670
Syringe nozzle, J. G. Fox.....	34,694
Tombstone or monument, E. C. Rodgers.....	34,681
Urn jar, E. Ney.....	34,697
Vase for cut flowers, R. Powell.....	34,690
Washstand, B. E. Caraway.....	34,671

### TRADE MARKS.

Acids and other liquid chemicals and gases N. P. Pratt Laboratory.....	36,905
Biscuits or crackers, H. W. Clark Biscuit Co. Blanks, covering, H. W. Clark Biscuit Co. Woolen Mills.....	36,911 36,902
Books, loose sheets and certain named at- tachments, blank, Baker-Vawter Co. Butter, K. H. Morgan.....	36,932 36,912
Butter, H. Chaloner & Co., Glasgow, Scot- land, bonbons, and loaves, except chocolate, Fohlman-Kipp Co.....	36,914 36,900
Cards, playing, United States Playing Card Co.....	36,934
Celluloid, hard rubber, and tortoise or of like nature and articles made thereof, raw materials or of Vegetable Gummiwaren-Fabrikten Harburg-Wien vormals Meier-J. N. Reithoffer.....	36,903 36,929
Coal, certain named, Carter, Curran & Hubert.....	36,920
Corn cures, W. K. Peck.....	36,908
Cotton goods, T. A. & Co.....	36,909
Flour, wheat, Acme Milling Co.....	36,915
Ice cream cakes, H. A. Haggard Co.....	36,916
Insulating papers, L. C. Marshall.....	36,953
Linoleum or wool fat and certain named lin- oleum preparations, mixtures and compounds, Norddeutsche Wollkammerei & Kam- mgarbepinner.....	36,904 36,901
Lenses, W. T. Georger.....	36,907
Medicine for certain named diseases, H. O. Winter.....	36,907
Musical instruments, self-playing attach- ments for keyboard, Farrand & Votey Organ Co.....	36,906 36,921
Pipes, fittings, valves and tools, certain named iron, John Simmons Co.....	36,912
Prunes, E. Corville.....	36,912
Remedy for certain named diseases, J. L. Smith & Son.....	36,906
Salt, Ohio Salt Co.....	36,917
Seeds, grain, vegetables, fertilizers, and seed covers, certain named, Albert Dickinson Co.....	36,919 36,901
Sheetings and drills, Greenwood Cotton Mill Shoes, ladies' and misses, Marks, Rothenberg & Co.....	36,906 36,908
Taffeta, Woodhouse, Bopp & Co.....	36,907
Underwear, Hay & Todd Manufacturing Co., Washing powders, W. A. Myser.....	36,907 36,918

### LABELS.

"Ashland Louse Killer," for an insecticide, Ashland Stock Food Co.....	8,470
"Ashland Stock Food," for a stock food, Ashland Stock Food Co.....	8,475
"Cairo," for a stock food, M. Walsman.....	8,477
"Chapman's Brain and Nerve Food," for a food, C. W. H. Chapman.....	8,468
"Claus Spreckels," for cigars, H. Plagemann & Co.....	8,474
"Eden," for a beverage, E. Eschbacher.....	8,464
"Ginseng," for a beverage, D. J. Kennedy.....	8,471
"Kenta," for cigars, Schmidt & Co.....	8,465
"Maltolfin," for a liquid extract, William Gerst Brewing Co.....	8,472
"Maple Belle," for cigars, Schmidt & Co.....	8,466
"Princess Patent Invisible Eye," for fastening books, Peet Bros.....	8,478
"Schlegel's Lustre Metal Polish," for metal polish, O. Schlegel.....	8,481
"Shuman," for a medicine, A. Edwards.....	8,467
"The Great Foot Elixir," for a medicine, Foot Elixir Co.....	8,470
"The New King," for shoes, H. Hirschberg.....	8,476
"White Crown," for cigars, J. Bels.....	8,463
"X-Ray," for a store polish, Blaser Manufacturing Co.....	8,480

### PRINTS.

"E-Z" for men's hats, J. Glashelm & Sons.....	302
"Hollan's American Horseshoe Pads," for horseshoe pads, M. Hallan.....	303

A printed copy of the specification and drawing of  
any patent in the foregoing list, or any patent in  
any issued since 1880, will be furnished from  
this office for 10 cents. In certain cases state  
the name and number of the patent desired, and  
remitt to Munn & Co., 361 Broadway, New York.  
Canadian patents may now be obtained by the  
inventors for any of the inventions named in the  
foregoing list. For terms and further particulars  
address Munn & Co., 361 Broadway, New York.

## Does 12% Interest You?

If it does, we would be pleased to have you send us your name and  
address, that we may send you a booklet which will tell you all about  
"Jupiter Steel Castings" and the "Neal Duplex Brake," as well as giving  
you full information concerning the Treasury Shares in this company,  
a block of which is now offered for sale at par value, \$5.00 per share.

For a year and a half quarterly dividends, at the rate of 12 per cent.  
per annum, have been paid on all the outstanding stock of this company,  
and this dividend rate will be increased as soon as we can enlarge our  
plant at Everett, Mass., to meet the needs of rapidly growing business.  
The plant which we now have at Everett cost us over \$250,000, but  
it is not large enough.

We have just received an order from the Fore River Ship and  
Engine Company for over one million pounds of Jupiter Steel Castings  
to be used in the construction of the New Battleships "Rhode Island"  
and "New Jersey," which this company is building for the United  
States Government. An order like this should mean something to every  
careful and sagacious investor.

## THE UNITED STATES STEEL CO.,

143 Oliver Street, BOSTON, MASS.

## PATENTS PROTECTED

AGAINST INFRINGERS.  
Dealers and Manufacturers of  
Patented Articles Protected  
against dangerous litigation at a  
nominal cost.  
Also Copyrights and Trademarks.  
Booklet on application.  
**PATENT TITLE & GUARANTEE CO.**  
Capital \$500,000.00.  
Telephone, 5533 Cortlandt.  
150 Broadway, New York.

## The Typewriter Exchange

114 Barclay St., NEW YORK  
124 La Salle St., CHICAGO  
38 Bromfield St., BOSTON  
817 Wyandotte St.,  
KANSAS CITY, MO.  
209 North 9th St.,  
ST. LOUIS, MO.  
432 Diamond St.,  
PITTSBURGH, PA.  
3 West Baltimore St.,  
BALTIMORE, MD.  
536 California St.,  
SAN FRANCISCO, CAL.  
We will save you from 10  
to 50% on Typewriters of all makes. Send for Catalogue.

FOR  
GUNSMITHS, TOOL  
MAKERS, EXPERI-  
MENTAL & REPAIR  
WORK, ETC.  
From 9-in. to 12-in. swing.  
Arranged for steam or  
Foot Power, Velociped  
or Stand-up Treadle.

**W. F. & John Barnes Co.,** 1099 Ruby St., Rockford, Ill.

The Improved  
BELL ODOMETER  
APPLIED TO YOUR  
AUTOMOBILE  
OR  
CARRIAGE  
will give you the exact distance traveled, and an-  
nounce each mile passed by the stroke of a bell.  
Send for Descriptive Circular S.  
**S. H. DAVIS & CO.**  
Cor. Portland & Sudbury Sts., Boston, Mass.

## SATISFACTION GUARANTEED.

## Acetylene Gas Generation PERFECTED.

The apparatus embodies en-  
tirely new principles. Safe,  
automatic, simple to install  
and operate. Next to daylight  
in cost and quality. Any capacity from table  
lamps to town plants. Also high grade "Crite-  
rion" stereopticons.

**J. B. COLT CO.,**  
Dept. S, 21 Barclay St., New York.  
Boston. Chicago. Philadelphia.

## DICKERMAN'S DURABLE DESKS

Don't buy until you get our catalogue—  
100 pages of money saving values.  
**AMERICAN STORE STOOL CO.,** 33 Howard St., New York

## BY-THE-BYE, WHEN YOU BUY A BICYCLE

be sure and buy the best,  
and that means the  
**BUFFALO KING.**  
"Buffalo King" is a lady.  
No better built wheels on  
the market—every rider  
satisfied. Thoroughly up  
to date in improvements.  
All parts of best material.  
Put together by skilled  
workmen. Prices \$25 and \$40. Illustrated Catalogue free on application.  
**THE W. M. HENDERER CO.,** Buffalo, N. Y., U. S. A.



## D. L. HOLDEN

"REAL ESTATE TRUST BLDG PHILA. PA."

## REGEALED ICE MACHINES

ALL FIRST PRIZE MACHINES AMERICAN MFG. CO. 1895

## AUTOMOBILE STEAM BOILERS

These Boilers are made of fire  
box steel, which has a tensile  
strength of 55,000 pounds. A  
double butt strap seam is used.  
The bottom end of shell is flanged  
to take flat head. This flange  
also takes care of difference in  
expansion between shell and  
copper tubes. Each boiler is  
tested to 80 pounds G. W. P.  
Can also furnish boilers with  
seamless cold drawn shell.

**FRANK MILNE, - - - EVERETT, MASS.**

## UPRIGHT DRILLS

Complete line, ranging from Light  
Friction Disk Drill to 4" Back Geared Self-  
Feed. Latest improvements. Up-to-date  
in every respect.

Send for Catalogue.  
Established 1878.

**W. F. & John Barnes Co.,** 1099 Ruby St., Rockford, Ill.

## The Improved BELL ODOMETER

will give you the exact distance traveled, and an-  
nounce each mile passed by the stroke of a bell.  
Send for Descriptive Circular S.

**S. H. DAVIS & CO.**  
Cor. Portland & Sudbury Sts., Boston, Mass.

## The Life of Machinery

depends on the careful treatment of it. Nothing so  
reduces the wear and tear and aids it in smoothly run-  
ning as

**DIXON'S**  
Pure-Flake  
Graphite.  
This lubricant reduces the  
chance of breakage, prevents  
much delay, is not affected by  
heat or cold, by acids or alkalis.  
It is sold regularly wherever  
once tried. Write for booklet.

**JOSEPH DIXON WRITABLE CO.**  
Jersey City, N. J.

**SHEET METAL NOVELTIES.**  
WE ARE PREPARED TO MAKE ARTICLES AND  
STAMPINGS OF ALL KINDS AND SIZES.  
T. CO. S. AND D. S. MANUFACTURED ON  
CONTRACT. FURNISH US BLUE PRINTS OR  
SAMPLES AND GET ESTIMATES.  
**STANDARD STAMPING CO.**  
DEPT. R. BUFFALO, N. Y.

## What Do You Want To Buy?

We can tell you where to buy anything you want.  
Write us for the addresses of manufacturers in ANY line of business.  
Novelties, Special Tools, Machinery, Equipments, New Patent LABOR SAVING DEVICES.  
**MUNN & CO.,** Publishers of the SCIENTIFIC AMERICAN, 361 BROADWAY, NEW YORK.



Our students succeed because they use  
I. C. S. textbooks.

## Steam Engineering

A course in Steam Engineering enabling students to pass examinations and secure better positions. Includes operation of dynamos and motors.

We teach by mail, Mechanical, Steam, Electrical, Civil and Mining Engineering; Ship and Foundry Practice; Mechanical Drawing; Architecture; Plumbing; Sheet Metal Work; Chemistry; Ornamental Design; Lettering; Bookbinding; Stenography; Teaching; English Branches; Locomotive Running; Electrotherapeutics.

When writing state subject in which interested.

### taught by mail.

International Correspondence Schools,  
Box 548, Scranton, Pa.

## ELECTRICAL ENGINEERING TAUGHT BY MAIL.

Write for our Free Illustrated Book.  
"CAN I BECOME AN ELECTRICAL ENGINEER?"

We teach Electrical Engineering, Electric Lighting, Electric Railways, Mechanical Engineering, Steam Engineering, Mechanical Drawing, at your home by mail. Institute founded by T. A. Edison and others.

**ELECTRICAL ENGINEER INSTITUTE,**  
Dept. A, 240-242 W. 234 St., New York.

## LIGHTNING CALCULATOR

Simplest and most perfect calculating machine made.

Introductory Price Only  
**\$3.00**

The kind of a machine for which you would expect to pay at least \$10. Money back if not satisfied.

best Calculator made for \$3.00.

All metal—Latest gun metal finish. Cannot get out of order. So simple a child can operate. So accurate that it is PERFECT. So light and portable it will go into your pocket.

The Lightning Calculator is used for verifying addition of long columns of figures, checking lengthy invoices, footing trial balances and proofwork, counting up mail order receipts, tallying all kinds of quantities, even additions, etc.

Accurate addition with no mental effort!

READ THIS!

Office PENNSYLVANIA RAILROAD CO., New York City, June 20, 1900.

The Book-Keeper Publishing Co., Ltd.  
GENTLEMEN: The Calculator received yesterday and am greatly pleased with the results of the little wonder. You will hear from me again in the near future.

Yours truly, JOHN B. POST.

Write today and take advantage of the \$3.00 price.

Agents Wanted.

THE BOOK-KEEPER PUBLISHING CO., Ltd.,  
Department O, DETROIT, MICH.

## Knox Gasoline Runabout.

Immediate Delivery.

WHY SO POPULAR?

Novel and improved engine.  
Entire absence of water.

Large carrying space in the body.

Ample power and all changes at speed.

100 miles on six gallons of fuel carried.

Used in all parts of the country.

Very reliable on account of its extreme simplicity.

Weight 675 Pounds.

Price \$750.

LIST OF AGENTS—A. F. UNDERHILL, 33 Stanhope Street, Boston, Mass.; SPALDING-BIRWELL CO., 22 West 42d Street, New York City; W. E. ROACHE, 201 Arch Street, Philadelphia, Pa.; A. G. SEALING & BROS., 147 Wabash Avenue, Chicago, Ill.; SCOTT AUTOMOBILE CO., 235 Olive Street, St. Louis, Mo.; FISHER CYCLE & AUTOMOBILE COMPANY, Delaware Street & Massena Avenue, Indianapolis, Ind.; KNOX AUTOMOBILE CO., - SPRINGFIELD, MASS.

## A NEW ENGLAND TRIO.

For years New England north from Boston has been frequented by the vacationist and health seeker. The first and most important feature which has made the region famous is the health-giving atmosphere; and this with delightful scenic surroundings, comfortable abiding places, an abundance of methods for diversion, coupled with unexcelled traveling facilities, suffice to make the territory a most superior and much sought outting place.

Northern New England is really divided into three principal resort regions, viz: Mountains, Sea Shore and Lakes; and for six cents in stamps the General Passenger and Ticket Agent of the Boston & Maine system, Boston, will send you a trip of booklet, known as "Among the Mountains," "Lakes and Streams," and "All Along Shore," and with them you will get a tour book which is overflowing with information of benefit to travelers in Maine, New Hampshire and Vermont. This company issues a variety of illustrated descriptive booklets which are listed in a readable index, and if you want to know about them, drop a postal to the above address.

For years New England north from Boston has been frequented by the vacationist and health seeker. The first and most important feature which has made the region famous is the health-giving atmosphere; and this with delightful scenic surroundings, comfortable abiding places, an abundance of methods for diversion, coupled with unexcelled traveling facilities, suffice to make the territory a most superior and much sought outting place.

## 50 YEARS' EXPERIENCE

# PATENTS

TRADE MARKS  
DESIGNS  
COPYRIGHTS &c.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. Handbook on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the

### Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all newsdealers.

**MUNN & Co.** 361 Broadway, New York  
Branch Office, 65 F St., Washington, D. C.

## SAVAGE MAGAZINE RIFLE

.303 and 30-30 Caliber.



The Rifle of the 20th Century

BAKER & HAMILTON, San Francisco and Sacramento, Cal.  
Pacific Coast Agents.  
SAVAGE ARMS CO., UTICA, N. Y., U. S. A.

The Only Hammerless Repeating Rifle. Smooth clean & accurate. One rifle for large and small game. Point blank range for hunting.

Write for New Catalogue A.

## WILLIAMS' SHAVING STICK

Famous for its rich creamy never drying lather

SOLD EVERYWHERE


Williams' Shaving Stick, - 25c.  
Yankee Shaving Soap (Round or Square), 10c.  
Luxury Shaving Tablet, - 25c.  
Swiss Violet Shaving Cream, - 50c.  
Williams' Shaving Soap (Barbers'), 6 Round Cakes, 1 lb., 40c. Exquisite also for toilet.

(Trial Size) Williams' Shaving Tablet for 2c. stamp "Stick" 10c.

The only firm in the world making a specialty of SHAVING SOAPS

THE J. B. WILLIAMS CO., Glastonbury, Ct.  
LONDON PARIS DRESDEN SYDNEY

## Remington Typewriters



are used by the heavy users

This is the supreme test of a typewriter. Good work on a brand new machine proves little or nothing. But it takes a first-class typewriter to keep doing good work, year after year, under the heaviest kind of service.

This is the secret of Remington supremacy. It accounts for the universal preference shown for the Remington by experienced users.

Wyckoff, Seamans & Benedict,  
327 Broadway, New York.

## OUTING FOR JULY MIDSUMMER NUMBER

Ancestry of the Coach

ILLUSTRATED IN FOUR COLORS  
BY EDWARD PENFIELD

Interesting and Timely Articles for

OUT-OF-DOOR COUNTRY-LIVING SPORT LOVING MEN and WOMEN

Write for SPECIAL OFFER TO NEW SUBSCRIBERS.

THE OUTING PUBLISHING COMPANY, 239 FIFTH AVENUE, NEW YORK.

Topic Topics:

## "THE NEW YORK CENTRAL"

IS THE

## "National Railroad of America."

In its issue of May 9, 1901, this item appears

"In the special issue of postage stamps to advertise the Buffalo Exposition the Post Office Department has done honor to the New York Central Railroad, the greatest mail carrier in the world. The one-cent stamp represents the lake navigation with which the Central Railroad connects; the two-cent stamp, the famous Niagara State Express train; the four-cent stamp, the automobiles used in the Central Railroad cab service; the five-cent stamp, the Niagara Falls bridge, past which the Central trains dash; the eight-cent stamp, the locks at Sault Ste. Marie, through which the Central Road steamers pass, and the ten-cent stamp, the ocean steamers with which the New York Central Lines connect and ticket passengers to every part of the globe. This unprecedented recognition by the Government establishes the New York Central as the National railroad of America."

## CREST MFG. CO.

CAMBRIDGEPORT, MASS.

### 3 to 5 H. P. MOTORS



Crest Sparking Plug  
Cells Batteries  
Carburetors

## PERFORATED METAL

OF EVERY DESCRIPTION  
AND FOR ALL USES.

THE HARRINGTON & KING PERFORATING CO., 225 UNION ST., CHICAGO, ILL., U.S.A.

## THE "KHOTAL"

is a Portable Practical Blue-Flame Oil Burning GAS STOVE



Available in city or country, on land or sea, anywhere that a supply of its fuel (kerosene) can be bought or carried; and that means everywhere!

Handsomely and strongly made of heavy brass and tinned iron; 8 1/4 inches high, 8 1/2 inches top diameter, weighs 4 1/2 lbs., never gets out of order.

Price, \$3.75

Other sizes—special finish for yachts—ovens, frames and accessories.

Send for descriptive pamphlet

Burns one quart of water in three minutes. Cooks a six-pound roast in a turn in 60 minutes.

It is the greatest of modern conveniences for camping, yachting, picnics; a hot-weather comfort in the household kitchen; capable of meeting any cooking requirement.

THE HYDROCARBON BURNER CO.  
197 Fulton Street, New York.

## WANTED

a firm to take up the manufacture and sale of

### PROCTOR'S

## Patent Mechanical Stokers and Self-Cleaning Bars

These inventions have been the subject of a great number of patents and may now be looked upon as complete and well-developed machines.

As a proof of the utility of this invention, 8,900 have been fitted up in England. Also one-fourth of this number have been renewed, many of which have been working so years, and a per cent. of the business is from old customers.

These patents can be taken up either on royalty or would sell for cash and small royalty.

Apply

JAS. PROCTOR,  
Hammerston Street Iron Works,  
Barnley, England.

## ICE MACHINES, Corlies Engines, Breweries' and Bottlers' Machinery, THE VILTER MFG. CO., 58 Clinton Street, Milwaukee, Wis.

## MODELS & EXPERIMENTAL WORK.

Inventions developed, Special Machinery.

E. V. BAILLARD, Fox Bldg., Franklin Square, New York.

## AGENTS.

—You can't find a better proposition. Honest business, large profits, advancement. Write us a chance to convince you. Lewis & Company, 28 North Third Street, St. Louis, Mo.

## AGENTS on salary or commission; \$10 daily or \$80 per month and expenses, selling our claim to merchants and physicians. Bayers & Company, 28 N. Olive Street, St. Louis, Mo.

## SHORTHAND BY MAIL.

Pioneer home course Catalogue and First Lesson Free.

Potts Shorthand College, Box 31, Williamsport, Pa.

## NEW YORK SHOPPING

by a responsible and experienced lady. Send for circular.

MRS. LORD, 55 West 26th Street, New York City.

## 1/2 H. P. GAS ENGINE CASTINGS

Materials and Blue Prints. Write for Catalogue.

PARNELL & WOOD, 123-124 W. 31st Street, New York.

## ROSE POLYTECHNIC INSTITUTE

A College of Engineering, Mechanical, Electrical, Civil Engineering; Chemical Courses; Architecture. Extensive shops. Modernly equipped laboratories in all departments. Expenses low. 15th year. For catalog, address C. L. MERES, President, Terre Haute, Ind.

## D'AMOUR & LITTLEDALE MACHINE CO.

130 WORTH ST., NEW YORK

PATTERN AND MODEL MAKERS.

Patent Rights for sale in the U. S. and foreign countries, on newly invented automatic Cor Coupler. Pronounced perfect. T. Y. HUGGELT, Kilmarnock, Va.

## STATLER'S Pap-American HOTEL

The Largest in the World. Send for map of city and Exposition grounds, also folder telling how to secure guaranteed accommodations.

F. C. STATLER, Prop.; Statler's Hotel, at Exposition, Buffalo, N. Y.; Statler's Restaurant, Elliott St. Bq.

## WANTED OFFERS

For anything new in the way of...

## AUTOMATIC MACHINERY

For the manufacture of

## Wire Fencing, Netting, Wire Cloth, etc.

Ray whether European Patents to be disposed of...

Address: "WIRE WORKER," Box 773, New York.

**THOROUGH INSPECTIONS**

AND INSURANCE AGAINST LOSS OF PROPERTY AND INJURY TO PERSONS CAUSED BY

**STEAM-BOILER-EXPLOSIONS**

J. A. ALLEN, President  
J. B. STURGES, Secretary  
J. M. ALLEN, Treasurer  
J. B. STURGES, Vice President  
J. M. ALLEN, Vice President  
J. B. STURGES, Vice President  
J. M. ALLEN, Vice President

## "The Four Hundred"



among American made automobiles are certainly the

**WINTON MOTOR CARRIAGES**

Most favored by society because they look better, run better, operate easier and are in every way superior to other machines. The same of high-grade manufacture. Strong, safe and durable. Hydro-Carbon System.

**THE WINTON MOTOR CARRIAGE CO.,**  
608 Holden Street, Cleveland, Ohio, U. S. A.  
BARTLEY DEPOT, 100-102 East 10th Street, New York.

"THIS WILL CARRY YOU."

## ELECTRIC VEHICLES OF ALL VARIETIES.

STORAGE

BATTERIES.

MOTORS.



We make a specialty of Delivery Wagons and Busses. Write for Catalogue.

**SCOTT AUTOMOBILE CO.,**

2927-2929 Olive Street, St. Louis, Mo., U. S. A.

## CHARTER ENGINE USED

ANY PLACE FOR ANY PURPOSE  
First-Class Gas, Oil, and Water  
Stationaries, Portables, Engines and Pumps, Hoisters  
Send for Catalogue and Testimonials.  
Make Your Power Needs



**CHARTER GAS ENGINE CO.,** Box 148, STERLING, ILL.



**BRISTOL'S RECORDING INSTRUMENTS.**  
Pressure Gauges, Vacuum Gauges, Voltmeters, Amperemeters, Wattmeters, and Thermometers, make continuous records day and night. Willing for themselves. Every instrument fully guaranteed and sent on 30 days' trial. Send for Circulars and Specimen Chart.  
The Bristol Company, Waterbury, Conn.

SILVER MEDAL PARIS EXPOSITION.

## GET A RUNNING GEAR and BUILD YOUR OWN AUTOMOBILE



We make two styles, solid rubber or pneumatic tires, complete with springs and wood wheels.

The Grecht Automobile Co., 1205 Cass Av., St. Louis, Mo.



**WATCHES!**  
No advertisement can properly portray the striking effects produced in our watches. They are illustrated in our BLUE BOOK showing Ladies' Watches in all metals and exquisite enamel; OR  
RED BOOK showing Men's and Boys' Watches with up-to-date attractive designs. Either Blue or Red Book sent on application.

**THE NEW ENGLAND WATCH CO.,**

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

37 & 39 Maiden Lane, New York City, 120 State Street, Chicago, Spreckels Building, San Francisco.

## WALTHAM WATCHES

Ralph Waldo Emerson in an essay on Eloquence said, in speaking of a man whom he described as a Godsend to his town, "He is put together like a Waltham Watch."

"The Perfected American Watch", an illustrated book of interesting information about watches, will be sent free upon request.

American Waltham Watch Company,  
Waltham, Mass.

# Columbia

## AUTOMOBILES

ELECTRIC

GASOLINE



Mark III Columbia Phaeton.

## EARLY DELIVERY OF 1901 MODELS

Equipped with

## NEW EXIDE BATTERIES

Excelling all others in

## CAPACITY AND DURABILITY FORTY MILES ON SINGLE CHARGE

To obtain the leading type of vehicle at moderate cost one should WRITE FOR 1901 ILLUSTRATED CATALOGUE AND PRICE LIST

Or call at

**ELECTRIC VEHICLE CO., 100 Broadway, New York.**

## "KODAK"

Stands for all that is Best in Photography

To the perfection of Kodak construction, to the perfection of the Kodak mechanism, to the perfection of the Kodak lenses, is due the

## Triumph of Kodakery

All Kodaks Load in Daylight with our Transparent Film Cartridges. Several styles use either films or plates. Sixty-four page catalogue, describing them in detail, free at the Kodak dealers or by mail.

**EASTMAN KODAK CO.**

Rochester, N. Y.

## JESSOP'S STEEL FOR TOOLS, SAWS, ETC.

WM. JESSOP & SONS, LTD. 31 JOHN ST. NEW YORK

## STEWARD'S WONDER

Is the highest class Acetylene Gas Burner. All Lava Tip. A new argand burner \$2.50—highest candle power obtainable. Correspondence solicited. STATE LINE MFG. CO., Chattanooga, Tenn., U. S. A.



**GARDNER GRINDER** FOR FLAT SURFACES. ACCURATELY RAPID. HBSLEY & CO. CHICAGO, ILL.

Scale. All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 100 useful articles, including Saws, Sewing machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.

## CRACKS IN FLOORS

are unsightly, unclean and unsanitary. **CRIPPIN'S WOOD, CRACK AND CHEVIE FILLER** is the only perfect remedy. A Paste, easily applied, elastic, adhesive, and non-shrinkable. Hirt and moth proof. Cost about 50c per sq. ft. 5 lbs. will treat an average room. Price 25c per lb. State the kind and condition of wood when ordering, and full instructions will be given. Is also the best filler for open-grained woods. **CRIPPIN MFG. CO.,** Lock Box 1, Newark, New York. (Inclose stamp for booklet.)


## THE LATEST TICKING MACHINE

Fun, Instruction and Navigation combined. By express \$1.00. By mail 25c extra. **R. I. Telephone & Electric Co.,** 22 Calender St., Providence, R. I.



## PRESIDENT SUSPENDERS

This shows the principle at the back of the President Suspenders. The only suspender made on a scientific, comfort-giving basis. Look for "President" on the buckle. Trimmings can not rust. Sold everywhere 50c., or by mail. **C. A. EDGARTON MFG. CO.,** Box 222, Shirley, Mass.



(VIEW OF TRAIN BEARING FOURTEEN GRIFFIN MILLS TO IOLA CEMENT CO.)

## "MOST SATISFACTORY AND ECONOMICAL."

**IOLA PORTLAND CEMENT COMPANY.**

**BRADLEY PULVERIZER CO., Boston, Mass.**

DETROIT, MICH., Oct. 16, 1900.

Gentlemen:—Your inquiry as to the satisfaction the Griffin Mills are giving us duly received. We have forty-two 30 in. Griffin Mills in our plant. The writer has had a large experience with most kinds of grinding machinery, and is prepared to say that for grinding Portland cement clinker the Griffin Mill is the most satisfactory and economical grinding machine on the market. Each of the above mills has at times run over ten barrels per hour, and on long runs has averaged nine and a half barrels each per hour.

We invite everyone interested in reducing refractory substances to an even degree of fineness to write for descriptive catalogue of this remarkable mill. It will surely interest you and may save you money.

**THE BRADLEY PULVERIZER CO., BOSTON.**



